

Contents

Report Volume – I

Foreword
 Preface
 Check List
 Salient Features
 Executive Summary
 List of Officers Associated in Preparation of DPR
 Index Map

Volume –I - Main Report

Para No.	Particulars	Page No.
	Chapter – 1	
	Introduction	
1.0	General	1
1.1	Outline of the Project	3
1.2	Justification and the Objective of the Project	9
1.3	Lessons Learned from Previous Projects	10
1.4	National Perspective Plan for Water Resources Development	13
1.5	Memorandum of Understanding between Centre and States and Inter- State Aspects	15
1.6	Selection of Proposed Scheme	18
1.7	Proposed Modification in Command area of Par-Tapi-Narmada Link Project	25
1.7.1	Need for Modification	25
1.7.2	Project Planning and Optimisation of Benefits	29
1.8	Methodology Adopted	35
1.8.1	Data Collection	35
1.8.2	Planning and Lay-out	36
1.8.2.1	Jheri Dam	36
1.8.2.2	Paikhed Dam	37
1.8.2.3	Chasmandva Dam	37
1.8.2.4	Chikkar Dam	38
1.8.2.5	Dabdar Dam	38
1.8.2.6	Kelwan Dam	38
1.8.2.7	Paikhed Barrage	39

Para No.	Particulars	Page No.
1.8.2.8	Chasmandva Barrage	39
1.8.2.9	Link Canal	39
1.8.2.10	Powerhouse	40
1.8.3	Surveys & Investigations	40
1.8.3.1	Survey & Investigation Works Carried out Departmentally	41
1.8.3.2	Survey and Investigation Works Carried out by Other Agencies	42
1.8.3.2.1	Topographical Surveys	42
1.8.3.2.2	Borrow Area Survey, Construction Material Survey and Testing of Rock Core Samples	43
1.8.3.2.3	Geological Survey	43
1.8.3.2.4	Drilling Works	43
1.8.3.2.5	Demarcation of Command Area En- route of the Link Canal	44
1.8.3.3	Technical Studies	44
1.8.3.3.1	Design of Important Project Components and writing of Design Chapter	44
1.8.3.3.2	Irrigation Planning	45
1.8.3.3.3	Construction Planning, Equipment Planning and Man-power Planning	45
1.8.3.3.4	Hydrological Study	45
1.8.3.3.5	Power Potential and Electrical & Mechanical Studies	45
1.8.3.3.6	Study of Seismic Parameter	45
1.8.3.3.7	Morphological Study	45
1.8.3.3.8	Mineral Surveys	46
1.8.3.3.9	Archaeological Surveys	46
1.8.3.3.10	Cadastral Surveys	46
1.8.3.3.11	Soil Surveys	46
1.8.3.4	Socio-economic Survey and Environmental Impact Assessment Studies	46
1.8.4	Engineering Assessment and Front End Engineering	47
1.8.4.1	Dam and Head Works	47
1.8.4.2	Tunnel Connecting Jheri and Paikhed Reservoir	49
1.8.4.3	Barrages	49
1.8.4.4	Link Canal	50

Para No.	Particulars	Page No.
1.8.5	Ecological, Socio-economic and Financial Aspects	51
1.8.6	Monitoring Mechanism	57
1.9	Clearances Required	58
	Chapter – 2 Physical Features	
2.1	Geographical Disposition	59
2.2	Topography of the Basins, Reservoirs and Command Area	59
2.2.1	Par Basin	59
2.2.2	Auranga Basin	60
2.2.3	Ambica Basin	61
2.2.4	Purna Basin	61
2.2.5	Tapi Basin	62
2.2.6	Narmada Basin	62
2.2.7	Topography of the Reservoirs	63
2.2.8	Topography of the Command Area	64
2.3	Geology of the Basin, Reservoir and Command Area	65
2.3.1	Geology of the Basins	65
2.3.2	Geology of Reservoirs	66
2.3.3	Geology of Command Area	68
2.4	River System and catchment Area	70
2.4.1	Par Basin	70
2.4.2	Auranga Basin	71
2.4.3	Ambica Basin	71
2.4.4	Purna Basin	72
2.4.5	Tapi Basin	73
2.5	Basin Characteristics	73
2.5.1	Rainfall	73
2.5.2	Temperature, Relative Humidity, Wind Speed and Cloud Cover	75
	Chapter – 3 Interstate Aspects	
3.1	States Traversed by the Rivers	76
3.2	Distribution of Catchment in State and Yields from the Catchment of the State Concerned	76
3.3 (a)	Effect on Project & of the Project on the Interstate Agreement on Sharing of Waters, Sharing the Benefits and Costs, Acceptance of Submergence in	79

Para No.	Particulars	Page No.
	the Upstream State Etc., if Any.	
3.3(b)	Effect on Project & of the Project on the Interstate Adjudication, if Any	84
3.3(c)	Effect on Project & of the Project on the Interstate Aspect of Territory, Property, etc. Coming Under Submergence, Project Affected People, Rehabilitation, Compensation, etc.	84
3.3 (d)	Effect on Project & of the Project on the Existing and Sanctioned Projects.	84
3.3 (e)	Any Other Aspect of the Project Involving Interstate Problems.	85
	Chapter – 4 Surveys and Investigations	
4.0	General	86
4.1	Topographical Surveys	91
4.1.1	Rivers	92
4.1.2	Reservoirs	95
4.1.3	Head Works	99
4.1.4	Plant and Colony Layout	104
4.1.5	Canal & Water Conductor System and Canal Structures	104
4.1.5.1	Alternative crossing of Tapi River without Dropping at Ukai Reservoir	105
4.1.6	Power House, Switch Yard, Surge shaft, Tailrace etc	105
4.1.7	Tunnel Survey	106
4.1.8	Command Area (detailed and sample)	106
4.1.8.1	Detailed topographical surveys for identification of en-route Command Area of link canal.	107
4.1.8.2	Sample Command Area surveys for OFD works	110
4.1.9	Soil Conservation	110
4.2	Other Surveys	111
4.2.1	Archaeological Survey in the Reservoir area	111
4.2.2	Mineral Survey in the Catchments/ Reservoir/Canals Area	111
4.2.3	Right of Way Survey for the Reservoirs	111
4.2.4	Communication Surveys	112
4.2.5	Drainage Survey	113
4.2.6	Soil Surveys	114

Para No.	Particulars	Page No.
4.3	Geology, Geophysical and Seismic Investigations	114
4.3.1.	Regional Geology	114
4.3.2	Local Geology	115
4.3.3	Geological Investigations	116
4.3.4	Seismicity	120
4.4	Sub-surface Geology and Foundation Investigations	122
4.4.1	Geophysical Investigations	131
4.5	Construction Material Investigations	135
4.5.1	Soils	135
4.5.2	Sand	137
4.5.3	Rock and Aggregates	137
4.5.4	Bricks and Tiles	138
4.5.5	Pozzolona	138
4.5.6	Cement	138
4.5.7	Steel	139
4.5.8	Scarce Material	139
4.5.9	Steel pipe of 2.5 To 2.9m dia	139
4.5.10	Any other Material	139
4.6	Hydrological and Meteorological Investigations	139
4.6.1	Rainfall	139
4.6.2	Discharge Data	142
4.6.3	Wind Speed	143
4.6.4	Humidity	143
4.6.5	Temperature	143
4.6.6	Sedimentation	143
4.6.7	Water Quality	145
4.6.8	Evaporation	146
4.6.9	Morphological Studies	146
	Chapter –5 Hydrology and Water Assessment	
5.0	General	147
5.1	General Climate and Hydrology	147
5.2	General Information about Regions	149
5.3	Specific Information	150
5.3.1	Drainage Basins	150
5.3.2	Command Area as per the Revised Irrigation Planning	152
5.3.3	Floods and Drainage	156

Para No.	Particulars	Page No.
5.3.4	River Geometry	157
5.3.5	Ground Water Recharge	158
5.3.6	Reservoir Area	158
5.3.7	Other Water Usage	162
5.3.8	Navigation	162
5.4	Data Availability	162
5.4.1	Rainfall and Snowfall	162
5.4.2	Pan Evaporation	170
5.4.3	Temperature, Relative Humidity, Wind Speed and Cloud Cover	171
5.4.4	River Gauge and Discharge	172
5.4.5	Sediment (Suspended and Bed Load) Inflow and Grain Size Composition	173
5.4.6	Water Quality	174
5.5	Hydrological Data Requirement	175
5.5.1	Alternatives and Classifications	175
5.6	Type of Inputs	175
5.6.1	Hydrological Inputs	175
5.7	Compilation and Processing of Basic Hydrological Data	176
5.7.1	Hydrological Investigation	176
5.7.2	Data from Other Sources	178
5.7.3	Processing of Data	178
5.7.3.1	Quality of Data	178
5.7.3.2	Filling of Short Data Gaps	178
5.7.4	Consistency of Data	179
5.7.4.1	Consistency Check of Rainfall Data	179
5.7.4.2	Weighted Mean Rainfall	180
5.7.4.3	Consistency Check for Discharge Data	185
5.7.5	Presentation of Data	205
5.7.5.1	Rainfall Data	205
5.7.5.2	Discharge / Yield Data	205
5.8	Water Availability / Inflows	206
5.8.1	Storage Projects	206
5.8.2	Approach in the Current Study	206
5.8.3	Hydrological Inputs required for Simulation	206
5.8.3.1	Water inflow in to Storage Reservoirs	207
5.8.3.2	Rainfall-Runoff Relationship	207
5.8.3.3	Gross Yield Series	213

Para No.	Particulars	Page No.
5.8.3.4	Net yield Series	215
5.8.3.5	Diversion and Small Pondages	217
5.9	Sedimentation Studies	218
5.9.1	Revised Area Capacity Curves	218
5.10	Potential Evapotranspiration and Rainfall	228
5.11	Inputs for Water Quality	228
5.12	Low Flow Inputs	229
5.13	Surface to Groundwater Recharge	229
5.14	Data for Studies other than Simulation	229
5.14.1	Design Flood and Diversion Flood Studies of Dams	229
5.14.1.1	Derivation of Unit Hydrograph	230
5.14.1.2	Design Storm Studies	235
5.14.1.3	Convolution	239
5.14.1.4	Design flood (PMF)	239
5.14.1.5	Diversion Flood	248
5.14.1.6	Conclusion	249
5.14.2	Design Flood and Diversion Flood Studies of Weirs	250
5.14.2.1	Derivation of Unit Hydrograph	251
5.14.2.2	Design Storm Studies	253
5.14.2.3	Convolution	257
5.14.2.4	Flood Hydrograph at Weir Sites	257
5.14.2.5	Conclusion	260
5.14.3	Tail water rating curves	261
5.15	Studies for design of drainage in the command area	264
5.16	Studies for Determination of Levels for Locating Structures on Outlets	265
5.16.1	Location of structures	265
5.16.2	Location of Outlets	266
5.17	Simulation Studies of the Reservoirs	270
5.17.1	Broad Criteria	270
5.17.2	Computation of Net Inflows in to the Reservoirs and Barrages	270
5.17.3	Priorities / Operation policy	281
5.17.4	Demands	282
5.17.4.1	Common Demands at Each Reservoirs	282
5.17.4.2	Project Specific Demands	283
5.17.5	Multi reservoir Simulation Study	286
5.17.5.1	Reservoir Operation Policy / Priorities	286

Para No.	Particulars	Page No.
5.17.5.2	Assumptions in the Simulation Study	287
5.17.6	Simulation Results and Observations	288
	Chapter –6 Design Aspects	
6.0	Engineering Assessment	291
6.1	General	291
6.1.1	Geology, Seismicity and Foundation	294
6.1.1.1	Geology	294
6.1.1.2	Seismicity	298
6.1.1.3	Foundation Treatment	298
6.1.2	Alternative Studies carried out for Selection of Site and Type of Structure	300
6.1.3	Choice of Final Layout of all Major Components of the Project and Reason	301
6.1.4	Design Flood and Sediment Studies	302
6.1.4.1	Design Flood Studies	302
6.1.4.2	Sediment Studies	303
6.1.4.3	Flood Routing Studies	304
6.1.5	Free Board for Fixing Top Elevation of Various Dams	306
6.1.5.1	Jheri Dam	306
6.1.5.2	Paikhed Dam	306
6.1.5.3	Chasmandva Dam	306
6.1.5.4	Chikkar Dam	307
6.1.5.5	Dabdar Dam	307
6.1.5.6	Kelwan Dam	307
6.1.5.7	Paikhed Barrage	308
6.1.5.8	Chasmandva Barrage	308
6.1.6	River Diversion Arrangements	308
6.1.7	Construction Materials	308
6.1.7.1	Rock / River Boulder Samples (Coarse Aggregate)	308
6.1.7.2	Fine Aggregate Samples	309
6.1.8	Details of Model Studies for Important Structures	310
6.2	Dam	310
6.2.1	Concrete Face Rock Fill Dam – Design Criteria and Stability Analysis	310

Para No.	Particulars	Page No.
6.2.1.1	General Layout	310
6.2.1.2	Background on Selection of CFRD	312
6.2.1.3	Attractive Features of a CFRD	313
6.2.1.4	Design of Typical Section of CFRDs	314
6.2.1.5	Dam Slope Stability	318
6.2.1.6	Plinth	318
6.2.1.7	Face Slab	319
6.2.1.7.1	Face Slab Thickness	320
6.2.1.7.2	Panel Width	320
6.2.1.7.3	Joints	321
6.2.1.7.3(a)	Parametric Joint and Water Stops	321
6.2.1.7.3(b)	Tensile Vertical Joint (Near Abutments) and Compressive Vertical Joint	322
6.2.1.7.3(c)	Horizontal Construction Joint	323
6.2.1.7.4	Concrete Properties	323
6.2.1.7.4(a)	Concrete Mix Design Properties	324
6.2.1.7.4(b)	Concrete Aggregates	324
6.2.1.7.5	Reinforcement	324
6.2.1.8	Parapet Wall	324
6.2.1.8.1	Joint between Parapet Wall and Face Slab	325
6.2.1.9	Interface Wall	325
6.2.1.10	Filter (Zone 2A) - Filter Requirements	326
6.2.2	Concrete Dam	328
6.2.2.1	Layout of Concrete Dam	328
6.2.2.2	Free Board	330
6.2.2.3	Zoning	330
6.2.2.4	Design of Concrete Dam	333
6.2.2.4.1	Design Criteria for Non- Overflow Section	333
6.2.2.4.2	Stability Analysis of Non-Overflow Section	334
6.2.2.4.3	Design of Overflow Section (Spillway)	341
6.2.2.4.4	Stability Analysis of Overflow Section	344
6.2.2.4.5	Chute Spillway	352
6.2.2.4.6	Energy Dissipation Arrangement	352
6.2.2.4.7	Curtain and Consolidation Grouting	353

Para No.	Particulars	Page No.
6.2.2.4.8	Spillway Gates	354
6.2.2.5	Opening through Dams	369
6.2.2.5.1	Gallery	369
6.2.2.5.2	Water Stop, Air Vent & Internal Drainage	369
6.3	Barrages and Head Regulators	370
6.3.1	Selection of Barrage Site	371
6.3.2	Design Flood	371
6.3.3	River Diversion for Paikhed and Chasmandva Barrage	359
6.3.4	Silt Factor	372
6.3.5	Assumed Retrogression at Maximum and Minimum Discharges	372
6.3.6	Pond Level	372
6.3.7	Waterway and HFL	372
6.3.8	Energy Dissipation Arrangement	373
6.3.9	Drainage and Anchorage Arrangements	373
6.3.10	Barrage Spillway Gates	373
6.3.10.1	Paikhed Barrage	373
6.3.10.2	Chasmandva Barrage	374
6.3.11	Barrage Spillway Stop Logs	374
6.3.11.1	Paikhed Barrage	374
6.3.11.2	Chasmandva Barrage	375
6.3.12	Gantry Crane for Stop Logs	376
6.3.12.1	Paikhed Barrage	376
6.3.12.2	Chasmandva Barrage	376
6.3.13	Road-Cum-Gantry Bridge, Trestle, etc.	376
6.3.14	Instruments and Remote Control	377
6.3.15	Diesel Generating Set	377
6.3.16	Weight Estimate for Gates and Operating Equipment	377
6.3.17	Protection Works	378
6.3.18	Seepage Control	378
6.3.19	Head Regulator, Service Gate and Stop Logs and Hoists	379

Para No.	Particulars	Page No.
6.3.19.1	Paikhed Barrage	379
6.3.19.2	Chasmandva Barrage	380
6.4	Jheri – Paikhed Link Tunnel	381
6.4.1	Layout of Link Tunnel	381
6.4.2	Hydraulic Design of the Link Tunnel	381
6.4.3	Intake Structure at Jheri Reservoir	382
6.4.4	Jheri to Paikhed Link Tunnel Details	384
6.4.5	Outfall Structure at Paikhed Reservoir	386
6.4.6	Hydro-Mechanical Equipment for Jheri-Paikhed Tunnel	386
6.4.6.1	Intake at Jheri reservoir	386
6.4.6.2	Outfall in Paikhed reservoir	387
6.4.6.3	Instruments and Remote Control	388
6.4.6.4	Diesel Generating Set	388
6.4.6.5	Weight Estimate for Gates and Operating Equipment	389
6.5	Canals	389
6.5.1	Description of Canal System	390
6.5.1.1	Canal Capacity	390
6.5.1.2	Canal Alignment	391
6.5.1.3	Details of Lining Provided	393
6.5.1.4	Transmission Losses	394
6.5.1.5	Sections and Reaches	394
6.5.1.6	Shape	394
6.5.1.7	Design Calculation for Adequacy of Canal Section	395
6.5.1.8	Canal Operation	400
6.5.2	Canal Structures	400
6.5.2.1	Cross Drainage Works / Regulators	400
6.5.2.1.1	Layout and Foundation	400
6.5.2.1.2	Cross Drainage	401
6.5.3	Study of Integrated Network of Canal System and its Operation	404
6.5.4	Description of Soil Profile along the Canal Alignment	404

Para No.	Particulars	Page No.
6.5.5	Broad Outline of Canal Automation and Branch Canals upto 8 Cumec	404
6.6	Power Houses	404
6.6.1 6.6.1	Surface Power house at Paikhed dam	405
6.6.1.1	Intake Structure	407
6.6.1.2	Pressure Shaft /Penstock	407
6.6.1.3	Tail race pool / Tail race channel	408
6.6.1.4	Power Intake Service & Emergency Gate	408
6.6.1.5	Draft Tube Gates	409
6.6.2	Surface Power house at Chasmandva Dam	410
6.6.2.1	Intake Structure	411
6.6.2.2	Penstock	412
6.6.2.3	Tail Race Pool / Channel	412
6.6.2.4	Power Intake Service & Emergency Gate	412
6.6.2.5	Draft Tube Gates	413
6.6.3	Surface Power House at Chikkar Dam	413
6.6.3.1	Intake Structure	415
6.6.3.2	Penstock	415
6.6.3.3	Tail Race Pool /Channel	416
6.6.3.4	Power Intake Service & Emergency Gate	416
6.6.3.5	Draft Tube Gates	417
6.6.4	Surface Power House at Dabdar Dam	417
6.6.4.1	Intake Structure	419
6.6.4.2	Penstock	419
6.6.4.3	Tail Race Pool / Channel	420
6.6.4.4	Power Intake Service & Emergency Gate	420
6.6.4.5	Draft Tube Gates	420
6.6.5	Surface Power House at Kelwan Dam	421
6.6.5.1	Intake Structure	423
6.6.5.2	Penstock	423
6.6.5.3	Tail Race Pool / Channel	423
6.6.5.4	Power Intake Service & Emergency Gate	424
6.6.5.5	Draft Tube Gates	424
6.6.6	Surface Power House of Kelwan Feeder Canal	425
6.6.6.1	Intake Structure	426
6.6.6.2	Penstock	427
6.6.6.3	Tail Race Pool	427
6.6.6.4	Feeder Canal Power House Intake Service & Emergency Gate	427

Para No.	Particulars	Page No.
6.6.6.5	Feeder Canal Draft Tube Gates	428
6.7	Instrumentation	428
6.8	Other Studies	429
	Chapter – 7 Reservoir	
7.0	General	430
7.1	Jheri Reservoir	432
7.1.1	Fixation of Storage and Reservoir Levels - Approach–Criteria	432
7.1.1.1	Dead Storage Level (DSL)	434
7.1.1.2	Low Water Level / Minimum Draw-Down Level (MDDL)	435
7.1.1.3	Full Reservoir Level (FRL)	435
7.1.1.4	Maximum Water Level (MWL)	436
7.1.1.5	Maximum Backwater Level at FRL and MWL and its Effect, Points to Which Backwater Effect is Felt. Maximum Distance of Such Points from the Axis of the Structure	436
7.1.1.6	Saddles along the Reservoir Rim	437
7.1.1.7	Fetch	437
7.1.1.8	Direction of Wind - Velocity of Wind - Wave Height - Free Board-Top of Dam	437
7.1.2	Sedimentation Data and Studies	437
7.1.2.1	Rate of Sedimentation with Basis	439
7.1.2.2	Quantity of Sediment	440
7.1.2.3	Type and Shape of Reservoir	440
7.1.2.4	Sediment Studies – Jheri Reservoir	440
7.1.2.5	Sediment Distribution	441
7.1.3	Life of Reservoir in Years with Basis	446
7.1.4	Capacity	446
7.1.4.1	Capacities of Jheri Reservoir	446
7.1.4.2	Storage	446
7.1.4.3	Water Tightness of the Reservoir	447
7.1.4.4	Annual Losses	448
7.1.4.5	Flood Absorption	448
7.1.5	Effects on Sub Soil Water Table in the Adjoining Areas Particularly Downstream of the Dam	448
7.1.6	Reservoir Rim Stability	448

Para No.	Particulars	Page No.
7.1.7	Area of Submergence	449
7.1.7.1	At Maximum Water Level	449
7.1.7.2	At Full Reservoir Level	449
7.1.7.3	Submergence Ratio - Submerged (Cultivated) Area / CCA	449
7.1.8	Land Acquisition-Property Submerged-Rehabilitation	449
7.1.8.1	Land Acquisition	449
7.1.8.2	Details of Property Submerged	450
7.1.8.3	Rehabilitation of Project Affected People	450
7.1.9	Recreation Facilities	452
7.1.10	Pisciculture	452
7.1.11	Need and Recommendation for Soil Conservation Measure in the Catchment	453
7.2	Paikhed Reservoir	453
7.2.1	Fixation of Storage and Reservoir Levels - Approach-Criteria	453
7.2.1.1	Dead Storage Level (DSL)	455
7.2.1.2	Low Water Level / Minimum Draw-Down Level (MDDL)	455
7.2.1.3	Full Reservoir Level (FRL)	455
7.2.1.4	Maximum Water Level (MWL)	456
7.2.1.5	Maximum Backwater Level at FRL and MWL and its Effect, Points to which Backwater Effect is Felt. Maximum Distance of such Points from the Axis of the Structure	456
7.2.1.6	Saddles along the Reservoir Rim	456
7.2.1.7	Fetch	457
7.2.1.8	Direction of Wind - Velocity of Wind - Wave Height - Free Board-Top of Dam	457
7.2.2	Sedimentation Data and Studies	457
7.2.2.1	Rate of Sedimentation with Basis	458
7.2.2.2	Quantity of Sediment	458
7.2.2.3	Type and Shape of Reservoir	458
7.2.2.4	Sediment Studies –Paikhed Reservoir	458
7.2.2.5	Sediment Distribution	458
7.2.3	Life of Reservoir in Years with Basis	463
7.2.4	Capacity	464

Para No.	Particulars	Page No.
7.2.4.1	Capacities of Paikhed Reservoir	464
7.2.4.2	Storage	464
7.2.4.3	Water Tightness of the Reservoir	465
7.2.4.4	Annual Losses	465
7.2.4.5	Flood Absorption	465
7.2.5	Effects on Sub Soil Water Table in the Adjoining Areas Particularly Downstream of the Dam	466
7.2.6	Reservoir Rim Stability	466
7.2.7	Area of Submergence	466
7.2.7.1	At Maximum Water Level	466
7.2.7.2	At Full Reservoir Level	466
7.2.7.3	Submergence Ratio - Submerged (Cultivated) Area / CCA	466
7.2.8	Land Acquisition-Property Submerged-Rehabilitation	467
7.2.8.1	Land Acquisition	467
7.2.8.2	Details of Property Submerged	467
7.2.8.3	Rehabilitation of Project Affected People	468
7.2.9	Recreation Facilities	468
7.2.10	Pisciculture	468
7.2.11	Need and Recommendation for Soil Conservation Measure in the Catchment	469
7.3	Chasmandva Reservoir	469
7.3.1	Fixation of Storage and Reservoir Levels - Approach-Criteria	469
7.3.1.1	Dead Storage Level (DSL)	470
7.3.1.2	Low Water Level / Minimum Draw-Down Level (MDDL)	471
7.3.1.3	Full Reservoir Level (FRL)	471
7.3.1.4	Maximum Water Level (MWL)	471
7.3.1.5	Maximum Backwater Level at FRL and MWL and its Effect, Points to Which Backwater Effect is Felt. Maximum Distance of Such Points from the Axis of the Structure	472
7.3.1.6	Saddles along the Reservoir Rim	472
7.3.1.7	Fetch	472
7.3.1.8	Direction of Wind - Velocity of Wind - Wave Height - Free Board-Top of Dam	473

Para No.	Particulars	Page No.
7.3.2	Sedimentation Data and Studies	473
7.3.2.1	Rate of Sedimentation with Basis	473
7.3.2.2	Quantity of Sediment	474
7.3.2.3	Type and Shape of Reservoir	474
7.3.2.4	Sediment Studies – Chasmandva Reservoir	474
7.3.2.5	Sediment Distribution	474
7.3.3	Life of Reservoir in Years with Basis	478
7.3.4	Capacity	478
7.3.4.1	Capacities of Chasmandva Reservoir	478
7.3.4.2	Storage	478
7.3.4.3	Water Tightness of the Reservoir	479
7.3.4.4	Annual Losses	480
7.3.4.5	Flood Absorption	480
7.3.5	Effects on Sub Soil Water Table in the Adjoining Areas Particularly Downstream of the Dam	480
7.3.6	Reservoir Rim Stability	480
7.3.7	Area of Submergence	481
7.3.7.1	At Maximum Water Level	481
7.3.7.2	At Full Reservoir Level	481
7.3.7.3	Submergence Ratio - Submerged (Cultivated) Area / CCA	481
7.3.8	Land Acquisition-Property Submerged-Rehabilitation	481
7.3.8.1	Land Acquisition	481
7.3.8.2	Details of Property Submerged	481
7.3.8.3	Rehabilitation of Project Affected People	482
7.3.9	Recreation Facilities	482
7.3.10	Pisciculture	483
7.3.11	Need and Recommendation for Soil Conservation Measure in the Catchment	483
7.4	Chikkar Reservoir	483
7.4.1	Fixation of Storage and Reservoir Levels - Approach–Criteria	483
7.4.1.1	Dead Storage Level (DSL)	485
7.4.1.2	Low Water Level / Minimum Draw-Down Level (MDDL)	485
7.4.1.3	Full Reservoir Level (FRL)	485
7.4.1.4	Maximum Water Level (MWL)	486
7.4.1.5	Maximum Backwater Level at FRL and MWL and	486

Para No.	Particulars	Page No.
	its Effect, Points to which Backwater Effect is Felt. Maximum Distance of such Points from the Axis of the Structure	
7.4.1.6	Saddles along the Reservoir Rim	486
7.4.1.7	Fetch	487
7.4.1.8	Direction of Wind - Velocity of Wind - Wave Height - Free Board-Top of Dam	487
7.4.2	Sedimentation Data and Studies	487
7.4.2.1	Rate of Sedimentation with Basis	488
7.4.2.2	Quantity of Sediment	488
7.4.2.3	Type and Shape of Reservoir	488
7.4.2.4	Sediment Studies –Chikkar Reservoir	488
7.4.2.5	Sediment Distribution	488
7.4.3	Life of Reservoir in Years with Basis	492
7.4.4	Capacity	493
7.4.4.1	Capacities of Chikkar Reservoir	493
7.4.4.2	Storage	493
7.4.4.3	Water Tightness of the Reservoir	494
7.4.4.4	Annual Losses	494
7.4.4.5	Flood Absorption	494
7.4.5	Effects on Sub Soil Water Table in the Adjoining Areas Particularly Downstream of the Dam	495
7.4.6	Reservoir Rim Stability	495
7.4.7	Area of Submergence	495
7.4.7.1	At Maximum Water Level	495
7.4.7.2	At Full Reservoir Level	495
7.4.7.3	Submergence Ratio - Submerged (Cultivated) Area / CCA	495
7.4.8	Land Acquisition-Property Submerged-Rehabilitation	496
7.4.8.1	Land Acquisition	496
7.4.8.2	Details of Property Submerged	496
7.4.8.3	Rehabilitation of Project Affected People	497
7.4.9	Recreation Facilities	497
7.4.10	Pisciculture	497
7.4.11	Need and Recommendation for Soil Conservation Measure in the Catchment	498
7.5	Dabdar Reservoir	498
7.5.1	Fixation of Storage and Reservoir Levels -	498

Para No.	Particulars	Page No.
	Approach–Criteria	
7.5.1.1	Dead Storage Level (DSL)	499
7.5.1.2	Low Water Level / Minimum Draw-Down Level (MDDL)	500
7.5.1.3	Full Reservoir Level (FRL)	500
7.5.1.4	Maximum Water Level (MWL)	500
7.5.1.5	Maximum Backwater Level at FRL and MWL and its Effect, Points to Which Backwater Effect is Felt. Maximum Distance of Such Points from the Axis of the Structure	501
7.5.1.6	Saddles along the Reservoir Rim	501
7.5.1.7	Fetch	501
7.5.1.8	Direction of Wind - Velocity of Wind - Wave Height - Free Board-Top of Dam	501
7.5.2	Sedimentation Data and Studies	502
7.5.2.1	Rate of Sedimentation With Basis	502
7.5.2.2	Quantity of Sediment	502
7.5.2.3	Type and Shape of Reservoir	503
7.5.2.4	Sediment Studies – Dabdar Reservoir	503
7.5.2.5	Sediment Distribution	503
7.5.3	Life of Reservoir in Years with Basis	508
7.5.4	Capacity	508
7.5.4.1	Capacities of Dabdar Reservoir	508
7.5.4.2	Storage	508
7.5.4.3	Water Tightness of the Reservoir	509
7.5.4.4	Annual Losses	509
7.5.4.5	Flood Absorption	509
7.5.5	Effects on Sub Soil Water Table in the Adjoining Areas Particularly Downstream of the Dam	510
7.5.6	Reservoir Rim Stability	510
7.5.7	Area of Submergence	510
7.5.7.1	At Maximum Water Level	510
7.5.7.2	At Full Reservoir Level	510
7.5.7.3	Submergence Ratio - Submerged (Cultivated) Area / CCA	510
7.5.8	Land Acquisition-Property Submerged-Rehabilitation	511
7.5.8.1	Land Acquisition	511

Para No.	Particulars	Page No.
7.5.8.2	Details of Property Submerged	511
7.5.8.3	Rehabilitation of Project Affected People	512
7.5.9	Recreation Facilities	512
7.5.10	Pisciculture	512
7.5.11	Need and Recommendation for Soil Conservation Measure in the Catchment	513
7.6	Kelwan Reservoir	513
7.6.1	Fixation of Storage and Reservoir Levels - Approach-Criteria	513
7.6.1.1	Dead Storage Level (DSL)	514
7.6.1.2	Low Water Level / Minimum Draw-Down Level (MDDL)	515
7.6.1.3	Full Reservoir Level (FRL)	515
7.6.1.4	Maximum Water Level (MWL)	515
7.6.1.5	Maximum Backwater Level at FRL and MWL and its Effect, Points to which Backwater Effect is Felt. Maximum Distance of such Points from the Axis of the Structure	516
7.6.1.6	Saddles along the Reservoir Rim	516
7.6.1.7	Fetch	516
7.6.1.8	Direction of Wind - Velocity of Wind - Wave Height - Free Board-Top of Dam	516
7.6.2	Sedimentation Data and Studies	517
7.6.2.1	Rate of Sedimentation with Basis	517
7.6.2.2	Quantity of Sediment	517
7.6.2.3	Type and Shape of Reservoir	518
7.6.2.4	Sediment Studies –Kelwan Reservoir	518
7.6.2.5	Sediment Distribution	518
7.6.3	Life of Reservoir in Years with Basis	523
7.6.4	Capacity	523
7.6.4.1	Capacities of Kelwan Reservoir	523
7.6.4.2	Storage	523
7.6.4.3	Water Tightness of the Reservoir	524
7.6.4.4	Annual Losses	524
7.6.4.5	Flood Absorption	525
7.6.5	Effects on Sub Soil Water Table in the Adjoining Areas Particularly Downstream of the Dam	525
7.6.6	Reservoir Rim Stability	525

Para No.	Particulars	Page No.
7.6.7	Area of Submergence	525
7.6.7.1	At Maximum Water Level	525
7.6.7.2	At Full Reservoir Level	525
7.6.7.3	Submergence Ratio - Submerged (Cultivated) Area / CCA	526
7.6.8	Land Acquisition-Property Submerged-Rehabilitation	526
7.6.8.1	Land Acquisition	526
7.6.8.2	Details of Property Submerged	526
7.6.8.3	Rehabilitation of Project Affected People	527
7.6.9	Recreation Facilities	527
7.6.10	Pisciculture	527
7.6.11	Need and Recommendation for Soil Conservation Measure in the Catchment	528
7.7	Ukai Reservoir (Existing)	528
7.8	Paikhed Barrage	529
7.9	Chasmandva Barrage	529
	Chapter – 8 Power	
8.0	General	530
8.1	Present Status of Power Development in Maharashtra and Gujarat States	530
8.1.1	Available Generating Capacity (MW) in the State/Region from different sources with location, category wise.	530
8.1.2	Present Status of Utilisation of Power Produced	535
8.1.3	Shortages / Surpluses and Import / Export of Power from/to the neighbouring States/Regions	536
8.1.4	Transmission System and Operation Voltages	537
8.2	Power requirements	538
8.2.1	Existing	538
8.2.2	Anticipated Requirements of energy (MU) and peak load (MW)	538
8.3	Future Plans of Power Development	538
8.4	Assessment of the Power Benefits from Par-Tapi-Narmada Link Project	541
8.4.1	Paikhed Dam Power House	543
8.4.1.1	Power Potential Study	543

Para No.	Particulars	Page No.
8.4.1.1.1	Type of Project	543
8.4.1.1.2	Hydrology, Sedimentation Studies and Criteria for Fixing up Reservoir Levels	544
8.4.1.1.3	Reservoir Operation	545
8.4.1.1.4	Simulation Studies	545
8.4.1.1.5	Firm Power	546
8.4.1.1.6	Installed Capacity	546
8.4.1.1.7	Scope for Seasonal/Secondary Power Generation	548
8.4.1.1.8	Size and Type of Generating Units	549
8.4.1.1.9	Number of Generating Units	549
8.4.1.2	Electrical & Mechanical Works	549
8.4.1.2.1	Turbine	550
8.4.1.2.2	Francis Turbine and Associated Equipments	551
8.4.1.2.3	Inlet Valves	552
8.4.1.2.4	Governing Equipment	553
8.4.1.2.5	Pressure Oil System	553
8.4.1.2.6	Generator	554
8.4.1.2.7	Electrical Control and Protection Equipments	557
8.4.1.2.8	Material Handling in the Power House	558
8.4.1.2.9	Auxiliary Power Supply	558
8.4.1.2.10	Cables and Boxes	559
8.4.1.2.11	Station Drainage System	559
8.4.1.2.12	Dewatering System	559
8.4.1.2.13	Ventilation System	560
8.4.1.2.14	Draft Tube Gate	560
8.4.1.2.15	Tailrace Channel	560
8.4.1.2.16	Switchyard	560
8.4.1.2.17	Grounding Systems	561
8.4.1.2.18	Transmission and Distribution Works	561
8.4.1.2.19	Drawings	562
8.4.1.2.20	Cost Estimate (S-Power Plant)	562
8.4.2	Chasmandva Dam Power House	563
8.4.2.1	Power Potential Study	563
8.4.2.1.1	Type of Project	563
8.4.2.1.2	Hydrology, Sedimentation Studies and Criteria for Fixing up Reservoir Levels	563
8.4.2.1.3	Reservoir Operation	565
8.4.2.1.4	Simulation Studies	565
8.4.2.1.5	Firm Power	565

Para No.	Particulars	Page No.
8.4.2.1.6	Installed Capacity	565
8.4.2.1.7	Scope For Seasonal/Secondary Power Generation	567
8.4.2.1.8	Size and Type of Generating Units	568
8.4.2.1.9	Number of Generating Units	568
8.4.2.2	Electrical & Mechanical Works	568
8.4.2.2.1	Turbine	569
8.4.2.2.2	Francis Turbine and Associated Equipments	570
8.4.2.2.3	Inlet Valves	571
8.4.2.2.4	Governing Equipment	572
8.4.2.2.5	Pressure Oil System	573
8.4.2.2.6	Generator	573
8.4.2.2.7	Electrical Control And Protection Equipments	576
8.4.2.2.8	Material Handling in the Power House	577
8.4.2.2.9	Auxiliary Power Supply	577
8.4.2.2.10	Cables and Boxes	577
8.4.2.2.11	Station Drainage System	577
8.4.2.2.12	Ventilation System	578
8.4.2.2.13	Draft Tube Gate	578
8.4.2.2.14	Tailrace Channel	578
8.4.2.2.15	Switchyard	578
8.4.2.2.16	Grounding Systems	579
8.4.2.2.17	Transmission and Distribution Works	579
8.4.2.2.18	Drawings	580
8.4.2.2.19	Cost Estimate (S-Power Plant)	580
8.4.3	Chikkar Dam Power House	581
8.4.3.1	Power Potential Study	581
8.4.3.1.1	Type of Project	581
8.4.3.1.2	Hydrology, Sedimentation Studies and Criteria for Fixing up Reservoir Levels	581
8.4.3.1.3	Reservoir Operation	583
8.4.3.1.4	Simulation Studies	583
8.4.3.1.5	Firm Power	583
8.4.3.1.6	Installed Capacity	583
8.4.3.1.7	Scope for Seasonal/Secondary Power Generation	585
8.4.3.1.8	Size and Type of Generating Units	585
8.4.3.1.9	Number of Generating Units	585
8.4.3.2	Electrical & Mechanical Works	586
8.4.3.2.1	Turbine	586
8.4.3.2.2	Francis Turbine and Associated Equipments	587

Para No.	Particulars	Page No.
8.4.3.2.3	Inlet Valves	589
8.4.3.2.4	Governing Equipment	590
8.4.3.2.5	Pressure Oil System	590
8.4.3.2.6	Generator	590
8.4.3.2.7	Electrical Control And Protection Equipments	593
8.4.3.2.8	Material Handling in the Power House	594
8.4.3.2.9	Auxiliary Power Supply	594
8.4.3.2.10	Cables and Boxes	595
8.4.3.1.11	Station Drainage System	595
8.4.3.2.12	Ventilation System	595
8.4.3.2.13	Draft Tube Gate	595
8.4.3.2.14	Tailrace Channel	595
8.4.3.2.15	Switchyard	596
8.4.3.2.16	Grounding Systems	596
8.4.3.2.17	Transmission and Distribution Works	596
8.4.3.2.18	Drawings	598
8.4.3.2.19	Cost Estimate (S-Power Plant)	598
8.4.4	Dabdar Dam Power House	598
8.4.4.1	Power Potential Study	598
8.4.4.1.1	Type of Project	598
8.4.4.1.2	Hydrology, Sedimentation Studies and Criteria for Fixing up Reservoir Levels	599
8.4.4.1.3	Reservoir Operation	600
8.4.4.1.4	Simulation Studies	600
8.4.4.1.5	Firm Power	601
8.4.4.1.6	Installed Capacity	601
8.4.4.1.7	Scope For Seasonal/Secondary Power Generation	603
8.4.4.1.8	Size and Type of Generating Units	603
8.4.4.1.9	Number of Generating Units	603
8.4.4.2	Electrical & Mechanical Works	603
8.4.4.2.1	Turbine	604
8.4.4.2.2	Francis Turbine and Associated Equipments	605
8.4.4.2.3	Inlet Valves	606
8.4.4.2.4	Governing Equipment	607
8.4.4.2.5	Pressure Oil System	607
8.4.4.2.6	Generator	607
8.4.4.2.7	Electrical Control And Protection Equipments	610
8.4.4.2.8	D.C. System	611
8.4.4.2.9	Fire Protection	611

Para No.	Particulars	Page No.
8.4.4.2.10	Material Handling in the Power House	612
8.4.4.1.11	Auxiliary Power Supply	612
8.4.4.2.12	Cables and Boxes	612
8.4.4.2.13	Station Drainage System	612
8.4.4.2.14	Ventilation System	612
8.4.4.2.15	Draft Tube Gate	613
8.4.4.2.16	Tailrace Channel	613
8.4.4.2.17	Switchyard	613
8.4.4.2.18	Grounding Systems	613
8.4.4.2.19	Transmission and Distribution Works	614
8.4.4.2.20	Drawings	615
8.4.4.2.21	Cost Estimate (S-Power Plant)	615
8.4.5	Kelwan Dam Power House	616
8.4.5.1	Power Potential Study	616
8.4.5.1.1	Type of Project	616
8.4.5.1.2	Hydrology, Sedimentation Studies and Criteria for Fixing up Reservoir Levels	616
8.4.5.1.3	Reservoir Operation	618
8.4.5.1.4	Simulation Studies	618
8.4.5.1.5	Firm Power	618
8.4.5.1.6	Installed Capacity	618
8.4.5.1.7	Scope For Seasonal/Secondary Power Generation	620
8.4.5.1.8	Size and Type of Generating Units	620
8.4.5.1.9	Number of Generating Units	620
8.4.5.2	Electrical & Mechanical Works	620
8.4.5.2.1	Turbine	621
8.4.5.2.2	Francis Turbine and Associated Equipments	622
8.4.5.2.3	Inlet Valves	623
8.4.5.2.4	Governing Equipment	624
8.4.5.2.5	Pressure Oil System	624
8.4.5.2.6	Generator	625
8.4.5.2.7	Electrical Control And Protection Equipments	627
8.4.5.2.8	D. C. System	628
8.4.5.2.9	Fire Protection	629
8.4.5.2.10	Material Handling in the Power House	629
8.4.5.2.11	Auxiliary Power Supply	629
8.4.5.2.12	Cables and Boxes	629
8.4.5.1.13	Station Drainage System	629
8.4.5.2.14	Ventilation System	630

Para No.	Particulars	Page No.
8.4.5.2.15	Draft Tube Gate	630
8.4.5.2.16	Tailrace Channel	630
8.4.5.2.17	Switchyard	630
8.4.5.2.18	Grounding Systems	630
8.4.5.2.19	Transmission and Distribution Works	631
8.4.5.2.20	Power evacuation	631
8.4.5.2.21	Step-up Transformers for the Switchyard	631
8.4.5.2.22	Transmission Lines	632
8.4.5.2.23	Drawings	632
8.4.5.2.24	Cost Estimate (S-Power Plant)	632
8.4.6	Power House on Kelwan Feeder Canal (Canal drop at RD 5.80 km)	633
8.4.6.1	Power Potential Study	634
8.4.6.1.1	Parameters used in Power Potential Study	634
8.4.6.1.2	Net Discharge	634
8.4.6.1.3	Firm Power	635
8.4.6.1.4	Installed Capacity	635
8.4.6.1.5	Scope for Seasonal/Secondary Power Generation	636
8.4.6.1.6	Size and Type of Generating Units	636
8.4.6.1.7	Number of Generating Units	637
8.4.6.2	Electrical & Mechanical Works	637
8.4.6.2.1	Turbine	637
8.4.6.2.2	Kaplan Turbine and Associated Equipments	638
8.4.6.2.3	Inlet Valves	639
8.4.6.2.4	Governing Equipment	640
8.4.6.2.5	Pressure Oil System	641
8.4.6.2.6	Generator	641
8.4.6.2.7	Electrical Control And Protection Equipments	644
8.4.6.2.8	Station Drainage System	646
8.4.6.2.9	Dewatering System	646
8.4.6.2.10	Ventilation System	646
8.4.6.1.11	Draft Tube Gate	646
8.4.6.2.12	Switchyard	647
8.4.6.2.13	Grounding Systems	647
8.4.6.2.14	Transmission and Distribution Works	648
8.4.6.2.15	Drawings	649
8.4.6.2.16	Cost Estimate (S-Power Plant)	649
	Chapter-9 Irrigation Planning and Command Area	

Para No.	Particulars	Page No.
	Development	
9.0	General	650
9.1	Existing/Proposed Irrigation Facilities in the Proposed Project Command Area	650
9.1.1	Proposed Irrigation Facilities in the Proposed Project Command Area	651
9.1.1.1	Command Area Proposed En-Route the Link Canal	652
9.1.1.2	Command Area of Projects suggested by Government of Gujarat.	657
9.1.1.3	Command area falling in Tribal area on right side of canal by lift.	658
9.1.1.4	Command area in the vicinity of six proposed reservoirs by Lift.	659
9.1.1.5	Command area of Tribal area on right side of Narmada Main canal by lift.	660
9.1.1.6	Command area of Miyagam Branch canal of Narmada Canal System	661
9.2	Existing Cropping Pattern	662
9.2.1	Existing Area Under Rain-Fed Cultivation	662
9.3	Soil Surveys	664
9.3.1	Soil Capability Classification	664
9.3.2	Land Irrigability Classification	665
9.4	Agro-Climatic Conditions	666
9.4.1	Rainfall	666
9.4.2	Temperature, Relative Humidity, Wind Speed and Cloud Cover	667
9.4.3	Frost free days	668
9.5	Proposed cropping pattern	668
9.5.1	Proposed irrigation facilities	671
9.5.1.1	En-route command	671
9.5.1.2	Command area proposed under Feeder Canals	672
9.5.1.3	Command Area of Narmada Main Canal (NMC) of SSP to be taken over by the Link Canal	672
9.5.2	Scope for double and multiple cropping pattern and change in cropping pattern on the basis of latest available data	674
9.5.2.1	Soils	674
9.5.2.1.1	Agro-climatic conditions	674
9.5.2.2	Water and other inputs like Fertilizers, Weedicides	674

Para No.	Particulars	Page No.
	and Pesticides	
9.5.2.3	Irrigated crops in the adjoining areas	674
9.5.2.4	Attitude of farmers towards modern irrigated agricultural practices	675
9.6	Crop water requirement	675
9.6.1	Monthly water requirement for irrigation	678
9.7	Water Planning	682
9.7.1	Surface water	682
9.7.1.1	Total irrigation demand of the link project	682
9.7.1.2	Domestic and Industrial use in the Periphery of Reservoirs	682
9.7.1.2.1	Supply of Drinking water for villages and filling of village and Panchayat tanks	682
9.7.1.4	Environmental Releases	682
9.7.1.5	Evaporation losses	683
9.7.1.6	Total water demand of the link project	683
9.7.1.7	Working Tables	684
9.7.1.8	Designed head discharge of canal systems	685
9.7.2	Ground water	686
9.7.2.1	Ground water quality	686
9.7.2.2	Conjunctive Use/ground water support	687
9.8	Command Area Drainage	687
9.9	Water Course / Field Channels	687
9.10	Water Management	688
9.10.1	Review and evaluation of existing system of operation and distribution in the command and/or in some adjoining projects, if any	688
9.10.2	Proposals for Participatory Irrigation Management including formation of water users Association	688
9.10.3	Scope of introduction of modern technology like sprinklers, drip irrigation etc	689
9.10.4	Existing practice of Department of Agriculture for popularizing micro irrigation	689
9.10.5	Facilities for training the operation and maintenance personnel at different levels of management & farmers-adequacy of existing facilities and proposals for augmentation	690
9.10.6	Existing extension activity & proposals for its improvement	690

Para No.	Particulars	Page No.
9.11	Command Area	691
9.11.1	Command Area Details	691
9.11.1.1	Location	691
9.11.1.2	Classification of land (forest, grass land, cultivable land, cultivable waste, barren land)	692
9.11.1.3	Size of land holding	693
9.11.1.4	Climate of Command Area	693
9.11.1.5	Irrigation	694
9.11.1.6	Socio-economic Aspects	695
9.11.1.7	Infrastructure facilities	696
9.11.1.8	Topography and soils	698
9.11.1.9	Ground Water and Drainage	699
9.11.1.10	Agriculture	700
9.11.1.11	Farmers' attitude towards improved agricultural practices	702
9.11.1.12	Identification of problems in en-route command area	703
9.11.1.13	Financial problems	704
9.11.1.14	Proposed cropping pattern with justification based on land irrigability classification, agro climatic conditions developed irrigated cropping pattern in adjoining project / area etc.	704
9.11.1.15	Land development work proposals	704
9.11.1.16	Ayacut roads	705
9.11.1.17	Benefits	705
9.11.2	Command area proposed under Feeder Canals	708
9.11.2.1	Benefits	708
9.11.3	Command Area of Projects Proposed by Government of Gujrat	710
9.11.4	Command of Tribal area enroute right side of canal, Tribal area in vicinity of reservoirs and Tribal area on right side of Narmada Main canal	713
9.11.4.1	Benefits	713
9.11.5	Command Area of Narmada Main Canal (NMC) of SSP to be taken over by the Link Canal – additional Irrigation in Saurashtra Region (Target Command) and Benefits	715
9.11.5.1	Benefits	715
	Chapter - 10 Construction Program, Man Power and Plant	

Para No.	Particulars	Page No.
	Planning	
10.0	General	718
10.1	Objective of the Project	718
10.2	Main Project Components	719
10.3	Basis for Study	721
10.3.1	General	721
10.3.2	Construction Material Sources	722
10.3.3	Basic Considerations	724
10.3.3.1	Scheduled Working Hours	724
10.3.3.2	Construction Period	725
10.4	Construction Methodology and Equipment planning	726
10.4.1	River Diversion Works	726
10.4.2	Jheri Dam	726
10.4.2.1	Concrete Face Rock-Fill Dam (Jheri Dam)	726
10.4.2.1(a)	Surface Excavation	727
10.4.2.1(b)	Fill Placement	729
10.4.2.1(c)	List of Major Construction Plant and Equipment for Jheri CFRD Dam	734
10.4.2.1(d)	Construction Programme	735
10.4.2.2	Concrete Dam (Jheri Dam)	736
10.4.2.2(a)	Surface Excavations	737
10.4.2.2(b)	Concreting	738
10.4.2.2(c)	List of Major Construction Plant and Equipment for Concrete Dam	738
10.4.2.2(d)	Construction Programme	739
10.4.3	Paikhed Dam	740
10.4.3.1	Concrete Face Rock-Fill Dam (Paikhed Dam)	740
10.4.3.1(a)	Surface Excavation	741
10.4.3.1(b)	Fill Placement	742
10.4.3.1(c)	List of Major Construction Plant and Equipment for CFRD Dam	747
10.4.3.1(d)	Construction Programme	748
10.4.3.2	Concrete Dam (Paikhed Dam)	748
10.4.3.2 (a)	Surface Excavations	749
10.4.3.2	Concreting	750

Para No.	Particulars	Page No.
(b)		
10.4.3.2(c)	List of Major Construction Plant and Equipment for Concrete Dam	750
10.4.3.2(d)	Construction Programme	751
10.4.3.3	Paikhed Dam Power House	752
10.4.3.3(a)	Excavation and Concreting	752
10.4.3.3(b)	List of Major Construction Plant and Equipment for Power House	753
10.4.3.3(c)	Construction Programme	753
10.4.4	Chasmandva Dam	753
10.4.4.1	Concrete Face Rock-Fill Dam (Chasmandva)	753
10.4.4.1 (a)	Surface Excavation	754
10.4.4.1	Fill Placement	756
(b)		
10.4.4.1(c)	List of Major Construction Plant and Equipment for CFRD Dam	760
10.4.4.1(d)	Construction Programme	761
10.4.4.2	Concrete Dam (Chasmandva)	762
10.4.4.2 (a)	Surface Excavations	762
10.4.4.2	Concreting	763
(b)		
10.4.4.2(c)	List of Major Construction Plant and Equipment for Concrete Dam	764
10.4.4.2	Construction Programme	765
(d)		
10.4.4.3	Chasmandva Dam Power House	765
10.4.4.3(a)	Excavation and Concreting	765
10.4.4.3(b)	List of Major Construction Plant and Equipment for Power House	766
10.4.4.3 (c)	Construction Programme	766
10.4.5	Chikkar Dam	767
10.4.5.1	Concrete Face Rock-Fill Dam (Chikkar)	767
10.4.5.1 (a)	Surface Excavation	768
10.4.5.1	Fill Placement	769
(b)		
10.4.5.1(c)	List of Major Construction Plant and Equipment for CFRD Dam	775
10.4.5.1(d)	Construction Programme	775
10.4.5.2	Concrete Dam (Chikkar)	776

Para No.	Particulars	Page No.
10.4.5.2 (a)	Surface Excavations	776
10.4.5.2 (b)	Concreting	777
10.4.5.2(c)	List of Major Construction Plant and Equipment for Concrete Dam	778
10.4.5.2 (d)	Construction Programme	779
10.4.5.3	Chikkar Dam Power House	779
10.4.5.3(a)	Excavation and Concreting	779
10.4.5.3(b)	List of Major Construction Plant and Equipment for Power House	780
10.4.5.3(c)	Construction Programme	781
10.4.6	Dabdar Dam	781
10.4.6.1	Concrete Face Rock-Fill Dam (Dabdar)	781
10.4.6.1(a)	Surface Excavation	782
10.4.6.1 (b)	Fill Placement	783
10.4.6.1(c)	List of Major Construction Plant and Equipment for CFRD Dam	788
10.4.6.1 (d)	Construction Programme	789
10.4.6.2	Concrete Dam (Dabdar)	790
10.4.6.2 (a)	Surface Excavations	790
10.4.6.2 (b)	Concreting	791
10.4.6.2 (c)	List of Major Construction Plant and Equipment for Concrete Dam	792
10.4.6.2 (d)	Construction Programme	793
10.4.6.3	Dabdar Dam Power House	793
10.4.6.3(a)	Excavation and Concreting	793
10.4.6.3 (b)	List of Major Construction Plant and Equipment for Power House	794
10.4.6.3 (c)	Construction Programme	794
10.4.7	Kelwan Dam	795
10.4.7.1	Concrete Face Rock-Fill Dam (Kelwan Dam)	795
10.4.7.1 (a)	Surface Excavation	796
10.4.7.1 (b)	Fill Placement	797

Para No.	Particulars	Page No.
10.4.7.1(c)	List of Major Construction Plant and Equipment for CFRD Dam	802
10.4.7.1 (d)	Construction Programme	803
10.4.7.2	Concrete Dam (Kelwan Dam)	804
10.4.7.2 (a)	Surface Excavations	804
10.4.7.2(b)	Concreting	805
10.4.7.2(c)	List of Major Construction Plant and Equipment for Concrete Dam	806
10.4.7.2 (d)	Construction Programme	807
10.4.7.3	Kelwan Dam Power House	807
10.4.7.3(a)	Excavation and Concreting	807
10.4.7.3(b)	List of Major Construction Plant and Equipment for Power House	808
10.4.7.3 (c)	Construction Programme	808
10.4.8	Barrages	809
10.4.8(a)	Paikhed Barrage & Head Regulator	809
10.4.8(a).1	Surface Excavation	809
10.4.8(a).2	Concreting	810
10.4.8(a).3	List of Major Construction Plant and Equipment for Paikhed Barrage	810
10.4.8(b)	Chasmandva Barrage & Head Regulator	811
10.4.8(b).1	Surface Excavation	811
10.4.8(b).2	Concreting	812
10.4.8(b).3	List of Major Construction Plant and Equipment for Chasmandva Barrage	813
10.4.9.1(a)	Chasmandva Canal	814
10.4.9.1(b)	List of Major Construction Plant and Equipment for Chasmandva Feeder Canal	815
10.4.9.1 (c)	Construction Programme	815
10.4.9.2(a)	Chikkar - Dabdar feeder canal	816
10.4.9.2(b)	List of Major Construction Plant and Equipment for Chikkar feeder canal	817
10.4.9.2 (c)	Construction Programme	818
10.4.9.3(a)	Dabdar Feeder Canal	819
10.4.9.3(b)	List of Major Construction Plant and Equipment for Dabdar Feeder Canal	820
10.4.9.3 (c)	Construction Programme	821

Para No.	Particulars	Page No.
10.4.9.4(a)	Kelwan Feeder Canal	821
10.4.9.4(b)	List of Major Construction Plant and Equipment for Kelwan Feeder Canal	823
10.4.9.4(c)	Construction Programme	823
10.4.10	Kelwan Dam Power House at the drop of Feeder Canal from Kelwan Reservoir	823
10.4.10(a)	Excavation and Concreting	823
10.4.10(b)	List of Major Construction Plant and Equipment for Power House	824
10.4.10 (c)	Construction Programme	824
10.4.11(a)	Par-Tapi Link Canal	825
10.4.11 (b)	List of Major Construction Plant and Equipment for Par-Tapi Link Canal	826
10.4.11 (c)	Construction Programme	827
10.4.12(a)	Tapi - Narmada Link Canal	828
10.4.12(b)	List of Major Construction Plant and Equipment for Tapi-Narmada Canal	830
10.4.12(c)	Construction Programme	831
10.4.13(a)	Jheri to Paikhed Link Tunnel	831
10.4.13(b)	Concrete Lining	834
10.4.13(c)	List of Major Construction Plant & Equipment for Construction of Jheri- Paikhed Link Tunnel	835
10.4.13 (d)	Construction Programme	836
10.4.14	Tunnels in Main Canal	836
10.4.14(a)	Excavation of Tunnel	836
10.4.14 (b)	Concrete Lining	838
10.4.14 (c)	List of Major Construction Plant & Equipment for Construction of tunnel in Main Canal	840
10.4.14(d)	Construction Program	841
10.5	Construction Program & Deployment Schedule	841
10.6	Manpower Planning	841
10.6.1	Organisation Setup	841
10.7	Year Wise Allocation of Cost	843
	Chapter - 11 Environment Impact Assessment and Environment Management Plan	
11.0	General	844

Para No.	Particulars	Page No.
11.1	The Proposed Project	844
11.1.1	Project Background	844
11.1.2	Project Justification	846
11.1.3	Project Description	847
11.2	Study Area	850
11.3	Legal Status of the Project	850
11.4	Baseline Environmental Data	852
11.4.1	Air Environment	853
11.4.1.1	Ambient Air Quality	853
11.4.1.2	Noise Environment	855
11.4.1.3	Meteorology	856
11.4.2	Water Quality	857
11.4.2.1	Surface Water Quality Monitoring	857
11.4.2.2	Ground Water Quality Monitoring	861
11.4.3	Land Environment	862
11.4.3.1	Land Use	862
11.4.3.2	Mineral Deposits	864
11.4.3.3	Historic / Archaeological Monuments	864
11.4.3.4	Geology	865
11.4.3.5	Soils	866
11.4.4	Terrestrial Ecology	871
11.4.4.1	Delineation of Flora in Study Area	871
11.4.4.2	Status of Fauna	874
11.4.4.3	Status of Fish Fauna	874
11.4.5	Public Health Facilities	875
11.4.6	Drinking Water Supply	878
11.5	Environmental Impact Assessment	878
11.5.1	Impacts on Air Environment	879
11.5.1.1	Impact on Air Quality	879
11.5.1.2	Impacts on Noise Environment	880
11.5.2	Impacts on Water Resources and Quality	880
11.5.3	Impacts on Land Environment	885
11.5.4	Impact on Biological Environment	888
11.5.4.1	Terrestrial Environment	888
11.5.4.1.1	Impacts on Forest Cover	888
11.5.4.2	Impacts on Wildlife	889
11.5.4.3	Impacts on Aquatic Ecology	889
11.5.4.4	Impact on Socio-economic Environment	891
11.5.5	Impacts On Micro Climate	893

Para No.	Particulars	Page No.
11.5.6	Greenhouse Gas Emission	893
11.6	Environmental Management Plan	894
11.6.1	Pollution Control at Construction Sites	894
11.6.1.1	Air Population Control	894
11.6.1.2	Noise Control Measures	897
11.6.2	Water Pollution	898
11.6.3	Land Management Plan	898
11.6.3.1	Disposal of Muck and Reclamation of Muck Disposal Sites	898
11.6.3.2	Restoration Plan for Quarry sites	899
11.6.3.3	Restoration of Colony and Office Complex	903
11.6.4	Biodiversity Conservation and Management Plan	904
11.6.4.1	Compensatory Afforestation	904
11.6.4.2	Biodiversity Management Plan	904
11.6.5	Green Belt Development Plan	911
11.6.6	Environmental Management in Labour Camps	912
11.6.7	Public Health	913
11.6.8	Catchment Area Treatment Plan	915
11.6.8.1	Approach for the study	915
11.6.8.2	Estimate of Soil loss using Silt Yield Index Method	916
11.6.8.3	Catchment Area Treatment measures	916
11.6.8.4	Silt Transfer	921
11.6.9	Disaster Management Plan	922
11.6.10	Energy Conservation Measures	923
11.6.10.1	Energy Conservation during Construction Phase	924
11.6.10.2	Energy Conservation during Operation Phase	924
11.6.10.3	Budget	925
11.6.11	Environmental Monitoring Programme	925
11.6.12	Cost of Environmental Management Plan	927
	Chapter - 12 Socio-Economic Studies and Resettlement and Rehabilitation Plan	
12.0	Introduction	929
12.1	Socio-Economic Profile and Survey	930
12.1.1	Regional Profile from the Available Secondary Data	931
12.1.1.1	Demography	933
12.1.1.2	Agriculture	933

Para No.	Particulars	Page No.
12.1.1.3	Literacy	934
12.1.2	Salient Features of the Link	934
12.1.3	Sample Design and Methodology	935
12.1.3.1	Selection of Villages	936
12.1.3.2	Selection of Households	937
12.1.4	Questionnaire	937
12.1.5	Profile of the Study Area	937
12.1.5.1	Jheri Reservoir	940
12.1.5.2	Paikhed Reservoir	946
12.1.5.3	Chasmandva Reservoir	953
12.1.5.4	Chikkar Reservoir	958
12.1.5.5	Dabdar Reservoir	965
12.1.5.6	Kelwan Reservoir	972
12.1.6	Perception about the Project	981
12.2	Impact of Par-Tapi-Narmada Link	981
12.2.1	Short-Term Impact of Link Project	982
12.2.2	Long-Term Impact of Link Project	982
12.2.3	Social Impact Assessment	983
12.2.3.1	Impacts Due to Land Acquisition	983
12.3	Rehabilitation and Resettlement	984
12.3.1	Assessment of Economic Loss Due to Displacement	985
12.3.1.1	Land under Submergence	985
12.3.1.2	Project Affected Community	986
12.3.2	People's Perception towards Rehabilitation Package	986
12.3.3	Rehabilitation and Resettlement Package	987
12.3.3.1	Measures for Resettlement	987
12.3.3.2	Measures for Rehabilitation	995
12.3.4	Local Area Development Plan	999
12.3.5	Monitoring and Evaluation	999
12.3.6	Cost of Rehabilitation & Resettlement Plan	1001
	Chapter – 13 Cost Estimate, Benefit Cost Ratio and Financial Aspects	
13.0	General	1003
13.1	Classification of Units	1005
13.1.1	Unit – I : Head Works	1007
13.1.1.1	Direct Charges	1008

Para No.	Particulars	Page No.
13.1.1.2	Indirect Charges	1013
13.1.2	Unit – II : Canal System	1013
13.1.2.1	Direct Charges	1014
13.1.2.2	Indirect Charges	1019
13.1.3	Unit – III : Hydroelectric Installation	1019
13.1.3.1	Direct Charges	1019
13.1.3.2	Indirect Charges	1021
13.1.4	Unit–IV: Navigation	1022
13.1.5	Unit–V: Water Supply Works	1033
13.1.6	Unit–VI: Command Area Development	1022
13.1.6.1	Direct charges	1025
13.2	Revenues	1025
13.2.1	Yearly Programme of Development w.r.t. Date of Starting of Construction of the Project	1025
13.2.2	Sources of Revenue	1026
13.2.2.1	Water Rates – Irrigation Cess	1026
13.2.2.2	Auction of Ferry Service, Inundated Land Lease, Auction for Fruit Bearing Trees along Canals, Lease of Land for Shops in Colony Area, Navigational Permits	1026
13.2.2.3	Revenue from Hydro-Power	1026
13.2.2.4	Revenue from Water Supply	1026
13.2.2.5	Navigation	1027
13.2.2.6	Other Sources (Pisciculture, Tourism etc.)	1027
13.2.3	Concession in Water Rates (Irrigation), Cargo and Passenger Rates, etc.	1027
13.2.4	Administrative Charges for Supply of Water and Collection of Revenues etc.	1027
13.2.5	If the Area to be Irrigated is Prone to Scarcity, the Expenditure Normally Incurred to Redress the Scarcity	1027
13.2.6	Year in Which the Revenue Would Start Accruing from Various Sources Counting from the First Year of Construction	1027
13.2.7	Total Income from Various Sources	1028
13.2.8	Details of Staff Proposed for Collection of Revenues and its Basis	1028

Para No.	Particulars	Page No.
13.2.9	Net Revenue Expected from Different Components of Project	1028
13.2.10	Productivity of Project in Terms of Percentage Financial Returns	1028
13.3	Benefit– Cost Ratio and Internal Rate of Return	1031
13.3.1	Estimate of Annual Cost	1031
13.3.2	Benefit Cost Ratio	1031
13.3.3	Internal Rate of Return (IRR)	1032
13.3.4	Benefit-Cost Ratio for flood control component of projects	1032
13.3.5	Benefits Other than those Considered in the Benefit-Cost Ratio and Internal Rate of Return	1032
	Chapter - 14 Other Aspects of the Project	
14.1	Foreign Exchange Element	1033
14.2	Revenue	1033
14.2.1	Revenue from Irrigation	1033
14.2.2	Revenue from Power	1034
14.2.3	Fisheries	1034
14.3	Financial Resources	1035
14.4	Future Utilisation of Facilities Created (Buildings)	1035
14.5	Legal Aspects of Par-Tapi-Narmada Link	1036
14.5.1	Effect of Par-Tapi-Narmada Link on the Territory of Other States	1036
14.5.2	Existing Interstate Agreement on Sharing of Water	1037
14.6	Sharing of Water and Hydro Power	1037
14.6.1	Water Sharing	1038
14.6.2	Power Sharing	1038
14.7	Feasibility of Utilisation of Water by Maharashtra State Across Western Divide by Lift	1039
	List of Abbreviations	1040

Volume – II
Annexures of Main Report

Annexure No.	Particulars	Page No.
1.1	Letter of Concurrence Received from Govt. of Maharashtra in respect of Par-Tapi-Narmada link	1
1.2	Letter of Concurrence Received from Govt. of Gujarat in respect of Par-Tapi-Narmada link	2
1.3	A Copy of Memorandum of Understanding (MoU) Signed By Hon'ble Chief Ministers of Gujarat and Maharashtra and Hon'ble Union Minister for Water Resources for Preparation of DPR of Damanganga - Pinjal & Par-Tapi-Narmada Links	3
1.4	A Copy of Letter No. NWDA/IC/V/T-85/2010/1383-86 dated 20.04.2010 Gist of discussion held by Director General, NWDA with Principle Secretary, Water Resources Department, Govt. of Gujarat, Gandhinagar Terminating the Par-Tapi-Narmada Link Canal at Existing Miyagam Branch Canal of Narmada Canal System	6
1.5	A Copy of Letter from Water Resources Department, Govt. of Gujarat, Gandhinagar Requesting to Carry out Survey and Investigations as Envisaged in Original Proposal of NWDA	8
1.6	A Copy of Letter from Principal Chief Conservator of Forest, Gandhinagar According Permission For	9

Annexure No.	Particulars	Page No.
	Carrying Out Survey & Investigations Work in the Forest Area in Gujarat State	
1.7	A Copy of Letter from Deputy Conservator of Forest (West), Nasik According Permission for Carrying Out Survey & Investigations Work in the Forest Area in Nasik District of Maharashtra	11
1.8	Constitution of the Committee for Empanelment of Consultant for Socio-Economic and Environmental Impact Assessment Studies- Office Order Dated 14/11/2008 Issued by NWDA Head Office	15
1.9	Modification in the Scope of the Committee for Empanelment of Consultants for EIA Studies- Office Order Dated 14/05/2009 Issued by NWDA Head Office	17
1.10	A Copy of MoEF letter No. J-12011/55/2008-IA.I Dated 8 th June 2009 Regarding ToRs for EIA Studies	19
1.11	A Copy of Letter Constituting the Committee to Monitor and Review the Progress of Work of EIA Studies - Office Order Dated 09/06/2010 Issued by NWDA Head Office	34
1.12	A Copy of Letter Reconstituting the Committee to Monitor and Review the Progress of EIA Studies of Damanganga - Pinjal and Par – Tapi - Narmada Link Projects under the Chairmanship of Chief Engineer (EMO), CWC, New Delhi	36
1.13	A Copy of MoWR's Office Order Constituting Monitoring Committee to Monitor and Supervise the Overall Work of Preparation of DPR of Damanganga - Pinjal & Par – Tapi - Narmada Link Projects	38
1.14	A Copy of MoWR's Letter Constituting Steering Committee to Review the Progress of Works of DPR of Damanganga - Pinjal and Par – Tapi - Narmada Link Projects	44
1.15	A Copy of Letter of Chief Engineer (S.G.)&	

Annexure No.	Particulars	Page No.
	Additional Secretary,Narmada Water Resources Water Supply & Kalpsar Department Govt. Of Gujarat, Gandhinagar dated 21.5.2016	
1.16	A Copy of Letter of Chief Engineer (S.G.)& Additional Secretary,Narmada Water Resources Water Supply & Kalpsar Department Govt. Of Gujarat, Gandhinagar dated 29.7.2016	
1.17	A copy of Minutes of Chief Engineers level Meeting held at New Sachivalaya, Gandhinagar on 11.11.2016 for firming up of Modifications in DPR of Par – Tapi - Narmada Link Project	
1.18	A copy of Minutes of Chief Engineers level Meeting held at New Sachivalaya, Gandhinagar on 09.02.2017 for firming up of Modifications in the DPR of Par - Tapi - Narmada Link Project	
4.1.1	Details of RCC Permanent Bench Marks Established in the Project Area of Par-Tapi-Narmada Link Project	45
4.1.2	Details of Temporary Bench Marks Established in the Project Area of Par-Tapi-Narmada Link Project	48
4 (A)	A Copy of Letter No. NWDA/Tech-I/200/44-14/mmeeting/09/Vol.I/126-32 dated 26 th June, 2012 from the Head office of NWDA – Minutes of the meeting held with CWC Regarding Dropping of Mohankavchali dam and Connecting Jheri Reservoir with Paikhed Reservoir by Tunnel	54 (A)
4.2.1	A Copy of Letter No.36/10/MIS/08-09/4078 dated 19 th Jun, 2009 from the Superintending Archaeologist, ASI, Vadodara – Regarding Archaeological Survey in the Gujarat Portion of Par-Tapi-Narmada Link Project	55
4.2.2	A Copy of Letter No.F No.12/2009-10/Tech-3036 dated 17 th Feb, 2011 from the Superintending Archaeologist, ASI, Aurangabad – Regarding Archaeological Survey in the Maharashtra Portion of Par-Tapi-Narmada Link Project	56
4.3	A Copy of Letter 171/G-1/EG/WR/GSI/08-09 dated 9 th April, 2009 from Engineering Geological	63

Annexure No.	Particulars	Page No.
	Division of Geological Survey of India, Jaipur - Regarding Mineral Survey	
4.4	A Copy of Letter No. 2/2/2012 (vol-I)/FE&SA/16 dated 4 th January, 2013 from FE&SA Directorate of CWC – Regarding Site Specific Design Earthquake Parameters for Par-Tapi-Narmada Link Project- Approved by NCSDP	64
4.5	Litho Logs of Bore Holes on Jheri Dam	67
4.6	Litho Logs of Bore Holes on Paikhed Dam	71
4.7	Litho Logs of Bore Holes on Chasmandva Dam	102
4.8	Litho Logs of Bore Holes on Chikkar Dam	130
4.9	Litho Logs of Bore Holes on Dabdar Dam	138
4.10.1	Test Results of Soil Sample Collected from Trial Pits on Jheri Dam Axis Area	146
4.10.2	Test Results of Soil Sample Collected from Trial Pits Upstream of Jheri Dam Axis Area	147
4.11	Test Results of Soil Sample Collected from Trial Pits Upstream of Paikhed Dam Axis Area	149
4.12.1	Test Results of Soil Sample Collected from Trial Pits on Chasmandva Dam Axis Area	151
4.12.2	Test Results of Soil Sample Collected from Trial Pits Upstream of Chasmandva Dam Axis Area	152
4.13.1	Test Results of Soil Sample Collected from Trial Pits on Chikkar Dam Axis Area	155
4.13.2	Test Results of Soil Sample Collected from Trial Pits Upstream of Chikkar Dam Axis Area	156
4.14.1	Test Results of Soil Sample Collected from Trial Pits on Dabdar Dam Axis Area	158
4.14.2	Test Results of Soil Sample Collected from Trial Pits Upstream of Dabdar Dam Axis Area	159
4.15.1	Test Results of Soil Samples from Trial pits on Kelwan Dam Axis Area	165
4.15.2	Test Results of Soil Samples from Trial pits on Upstream of Kelwan Dam Axis Area	166
5.1	Gross Yield Series upto Railway Bridge Site	168
5.2	Gross Yield Series at Jheri Dam Site on Par River	169
5.3	Gross Yield Series at Paikhed Dam Site on Par	170

Annexure No.	Particulars	Page No.
	River	
5.4	Gross Yield Series for whole Auranga Basin.	172
5.5	Gross Yield Series at Chasmandva Dam Site on Tan River (Tributary of Auranga River)	173
5.6	Gross Yield Series for whole Ambica Basin.	174
5.7	Gross Yield Series at Chikkar Dam Site on Ambica River	175
5.8	Gross Yield Series at Dabdar Dam Site on Khapri River (Tributary of Ambica River)	176
5.9	Gross Yield Series for whole Purna Basin.	177
5.10	Gross Yield Series at Kelwan Dam Site on Purna River	178
5.11	Net Yield Series at Jheri Dam Site on Par River	179
5.12	Net Yield Series at Paikhed Dam Site on Par River	180
5.13	Net Yield Series at Chasmandva Dam Site on Tan River (Tributary of Auranga River)	182
5.14	Net Yield Series at Chikkar Dam Site on Ambica River	183
5.15	Net Yield Series at Dabdar Dam Site on Khapri River (Tributary of Ambica River)	184
5.16	Net Yield Series at Kelwan Dam Site on Purna River	185
5.17	Minutes of 1 st Meeting Held on 23 rd September, 2011 between the States of Gujarat and Maharashtra at the Level of Chief Engineers on Sharing of Damanganga Water	186
5.18	Minutes of 2 nd Meeting Held on 14 th June, 2013 between the States of Gujarat and Maharashtra at the Level of Chief Engineers on Sharing of Damanganga Water	193
5.19	Minutes of 3 rd Meeting Held on 17 th June, 2014 between the States of Gujarat and Maharashtra at the Level of Chief Engineers on Sharing of Damanganga Water	203
6.1	Salient Features of Spillway Radial Gate at Jheri Dam	211
6.2	Salient Features of Spillway Stop log at Jheri Dam	212

Annexure No.	Particulars	Page No.
6.3	Tentative Weight Estimate of Hydro mechanical Equipment of Jheri Dam	213
6.4	Salient Features of Spillway Radial Gate at Paikhed Dam	214
6.5	Salient Features of Spillway Stoplogs at Paikhed Dam	215
6.6	Tentative Weight Estimate of Hydro mechanical Equipment of Paikhed Dam and Paikhed Power House	216
6.7	Salient Features of Spillway Radial Gate at Chasmandva Dam	218
6.8	Salient Features of Spillway Stoplogs at Chasmandva Dam	219
6.9	Tentative Weight Estimate of Hydro mechanical Equipment of Chasmandva Dam	220
6.10	Salient Features of Spillway Radial Gate at Chikkar Dam	222
6.11	Salient Features of Spillway Stoplogs at Chikkar Dam	223
6.12	Tentative Weight Estimate of Hydro mechanical Equipment of Chikkar Dam	224
6.13	Salient Features of Spillway Radial Gate at Dabdar Dam	226
6.14	Salient Features of Spillway Stoplogs at Dabdar Dam	227
6.15	Tentative Weight Estimate of Hydro mechanical Equipment of Dabdar Dam and Dabdar power House	228
6.16	Salient Features of Spillway Radial Gate at Kelwan Dam	229
6.17	Salient Features of Spillway Stoplogs at Kelwan Dam	230
6.18	Tentative Weight Estimate of Hydro mechanical Equipment of Kelwan Dam , Kelwan Dam toe PH and Kelwan Feeder canal PH	231
6.19	Salient Features of Spillway Radial Gate at Paikhed Barrage	233
6.20	Salient Features of Spillway Radial Gate at Chasmandva Barrage	234
6.21	Salient Features of Spillway Stoplogs at Paikhed	235

Annexure No.	Particulars	Page No.
	Barrage	
6.22	Salient Features of Spillway Stoplogs at Chasmandva Barrage	236
6.23(a)	Tentative Weight Estimate of Hydromechanical Equipment for Paikhed Barrage	237
6.23(b)	Tentative Weight Estimate of Hydromechanical Equipment for Chasmandva Barrage	239
6.24	Tentative Weight Estimate of Hydro mechanical Equipment for Canal Head Regulator & Cross Regulator at D/S of Ukai Dam	241
6.25	Salient Features of Spillway Radial Gate at Paikhed Head Regulator	242
6.26	Salient Features of Stop Logs for Paikhed Head Regulator Service Gate	243
6.27	Salient Features of Spillway Radial Gate at Chasmandva Head Regulator	244
6.28	Salient Features of Stop Logs for Chasmandva Head Regulator Service Gate	245
6.29	Salient Features of Intake Service Gate at Jheri Dam	246
6.30	Salient Features of Emergency Service Gate at Jheri Dam	247
6.31	Salient Features of Intake Service Gate at Paikhed Dam	248
6.32	Salient Features of Emergency Service Gate at Paikhed Dam	249
6.33	Tentative Weight Estimate of Hydromechanical Equipment for Jheri- Paikhed Link Tunnel	250
6.34	Hydraulic Particulars of Canal	251
6.35	Hydraulic Particulars of Feeder Canals	252
6.36	Salient Features of Power Intake Service Gate at Paikhed Dam Power House	253
6.37	Salient Features of Power Intake Emergency Gate at Paikhed Dam Power House	254
6.38	Salient Features of Draft Tube Gate at Paikhed Dam Power House	255
6.39	Salient Features of Power Intake Service Gate at Chasmandva Dam Power House	256
6.40	Salient Features of Power Intake Service Emergency Gate at Chasmandva Dam Power House	257

Annexure No.	Particulars	Page No.
6.41	Salient Features of Draft Tube Gate at Chasmandva Dam Power House	258
6.42	Salient Features of Power Intake Service Gate at Chikkar Dam Power House	259
6.43	Salient Features of Power Intake Emergency Gate at Chikkar Dam Power House	260
6.44	Salient Features of Draft Tube Gate at Chikkar Dam Power House	261
6.45	Salient Features of Power Intake Service Gate at Dabdar Dam Power House	262
6.46	Salient Features of Power Intake Emergency Gate at Dabdar Dam Power House	263
6.47	Salient Features of Draft Tube Gate at Dabdar Dam Power House	264
6.48	Salient Features of Power Intake Service Gate at Kelwan Dam Power House	265
6.49	Salient Features of Power Intake Emergency Gate at Kelwan Dam Power House	266
6.50	Salient Features of Draft Tube Gate at Kelwan Dam Power House	267
6.51	Salient Features of Power Intake Service Gate at Kelwan Feeder Canal Power House	268
6.52	Salient Features of Power Intake Emergency Gate at Kelwan Feeder Canal Power House	269
6.53	Salient Features of Draft Tube Gate at Kelwan Feeder Canal Power House	270
9.1 to 9.23	Annexures of Irrigation Planning of Par-Tapi-Narmada link project prepared by Irrigation Planning (South) Directorate, CWC, New Delhi	271 (1-106)
9.24	A copy of letter No. F.No./Tech/Gh-4/Par-Tapi-Narmada link Pro./1806/2015 dated 21.04.2015 from State Agricultural Department Regarding Approval for the suggested Cropping pattern in the En-Route Command of Par-Tapi-Narmada Link Project.	272
9.25	The District wise total Utilisable/Extractable Ground Water Availability and Net Draft in the Command Area in Pre & Post Project Scenario.	274
10.1	Detailed Construction Schedule of Par-Tapi-Narmada Link Project	276

Annexure No.	Particulars	Page No.
10.2	Deployment Schedule of Major Construction Equipments Required for the Project	279
10.3.1 to 10.3.7	Proposed Organisational Chart for Execution of the Project	281
10.4	Abstract of Requirement of Staff	288
10.5	Requirement of Staff (Other than Field Staff)	289
10.6	Requirement of fund for the scheme and its Yearly Phasing	299
12.1	Household Interview Survey	304
12.2	Village Survey Schedule	311
13.1	Abstract of Cost of Unit-I Head Works	322
13.2	Abstract of Cost of Unit-II Canal System	323
13.3	Abstract of Cost of Unit-III Power House	324
13.4	Abstract of Cost of Unit-VI Command Area Development Works	325
13.5	Calculation of Benefit - Cost ratio (Project as a Whole)	326
13.6	Internal Rate of Return (IRR)	327
14.1	Executive Summary of Alternative proposal to utilise Maharashtra portion of water contributing to Par-Tapi-Narmada link by lift across Western Ghats.	330
14.2	Salient Features of Alternative proposal to utilise Maharashtra portion of water contributing to Par-Tapi-Narmada link by lift across Western Ghats.	332
14.3	Index Map of Alternative proposal to utilise Maharashtra portion of water contributing to Par-Tapi-Narmada link by lift across Western Ghats.	334
14.4	A Copy of the Letter No. NWDA/CE(S)/IS Links/DG(Ek) –GV/2010-DB/284-88 Dated 18 th April, 2011 Addressed to the Secretary, Water Resources Department, Government of Maharashtra – Circulation of PFR of Nar Par-Girna Link Project, an Intrastate Link Project of Maharashtra	335

Volume – III
Appendices - Surveys and Investigations

Appendix No.	Title
4.1	RRSC, Jodhpur Report No. RRSCN/TR/2011/1- Regarding Demarcation of Command Area en-route Par-Tapi-Narmada link.
4.2	Report on Preliminary Geotechnical Investigation for Par-Tapi-Narmada Link Project of National Water Development Agency in the Dangs & Valsad Districts of Gujarat and Nasik District Maharashtra (Field Season 1993 - 94).
4.3	Report on Estimation of Site Specific Design Ground Motion (Seismic) Study of Par-Tapi-Narmada Link Project (CWPRS Report No. 4848).
4.4	Interim Report on Geophysical Surveys for Par-Tapi-Narmada Link Project of National Water Development Agency in Dang and Valsad Districts of Gujarat and Nasik District of Maharashtra (Field Season 1993-94).
4.5	The Report of GSI on geotechnical investigations at Paikhed and Chasmandava dam sites carried out at DPR stage(Field Season 2009-10).
4.6	The report on laboratory investigations of Rock core samples from Paikhed Dam Area Submitted by CSMRS, New Delhi (CSMRS Report No. 2/RM-I/CSMRS/E/4/2011of April, 2011).
4.7	The report on laboratory investigations of Rock core samples

Appendix No.	Title
	from Chasmandva Dam Area Submitted by CSMRS, New Delhi (CSMRS Report No. 1/RM-I/CSMRS/E/4/2011 of April, 2011).
4.8	Report on Sub-Surface Exploration at the Chikkar Dam Site of Par-Tapi- Narmada Link Project, of National Water Development Agency, in District The Dangs, Gujarat (Field Season 1994-95).
4.9	The report of CSMRS bearing No. C-I/CSMRS/E/04/2014- Regarding Construction Material Survey and Investigations of Coarse and Fine Aggregate Samples for Par-Tapi-Narmada Link Project.
4.10	Morphological Studies of Par-Tapi-Narmada Link Project using Remote Sensing and GIS Technology (RRSC Report No. RRSCN/TR/2013/01).

Volume – IV

Appendices – Hydrology and Water Assessment

Appendix No.	Title
5.1	Water Availability Study Report of Par-Tapi-Narmada Link Project (CWC Report - March 2012)
5.2	Sedimentation Study Report of Par-Tapi-Narmada Link Project (CWC Report – July 2013)
5.3	Design Flood and Diversion Flood Studies at Dams of Par-Tapi-Narmada link project (CWC Report – October 2012)
5.4	Design Flood and Diversion Flood Studies at Weirs of Par-Tapi-Narmada link project (CWC Report - January 2014)
5.5	Simulation Studies of Reservoirs Involved in Par-Tapi-Narmada Link Project (Prepared by NWDA)

Volume – V
Appendices –Power

Appendix No.	Particulars
8.1	Report on Power Potential Study of Paikhed Dam Power House of Par-Tapi-Narmada Link Project (THDCIL Report – Jan 2015)
8.2	Report on Power Potential Study of Chasmandva Dam Power House of Par-Tapi-Narmada Link Project (THDCIL Report – Jan 2015)
8.3	Report on Power Potential Study of Chikkar Dam Power House of Par-Tapi-Narmada Link Project (THDCIL Report – Jan 2015)
8.4	Report on Power Potential Study of Dabdar Dam Power House of Par-Tapi-Narmada Link Project (THDCIL Report – Jan 2015)
8.5	Report on Power Potential Study of Kelwan Dam Power House of Par-Tapi-Narmada Link Project (THDCIL Report – Jan 2015)
8.6	Report on Power Potential Study of Kelwan Feeder Canal Power House of Par-Tapi-Narmada Link Project (THDCIL Report – Jan 2015)
8.7	Report on Electrical and Mechanical (E&M) Study of Paikhed Dam of Par-Tapi-Narmada Link Project (THDCIL Report – Feb 2015)
8.8	Report on Electrical and Mechanical (E&M) Study of Chasmandva Dam of Par-Tapi-Narmada Link Project (THDCIL Report – Feb 2015)
8.9	Report on Electrical and Mechanical (E&M) Study of Chikkar Dam of Par-Tapi-Narmada Link Project (THDCIL Report – Feb

	2015)
8.10	Report on Electrical and Mechanical (E&M) Study of Dabdar Dam of Par-Tapi-Narmada Link Project (THDCIL Report – Feb 2015)
8.11	Report on Electrical and Mechanical (E&M) Study of Kelwan Dam of Par-Tapi-Narmada Link Project (THDCIL Report – Feb 2015)
8.12	Report on Electrical and Mechanical (E&M) Study of Kelwan Feeder Canal of Par-Tapi-Narmada Link Project (THDCIL Report – Feb 2015)

Volume – VI (A)

Appendices - Cost Estimate

Annexure No.	Title	Page No.
13.0	General Abstract of Cost	1
13.1	General Abstract of Unit-I Head Works	2
13.1.1	A - Preliminary	3
13.1.2	B - Land	4
13.1.3	C - Works	7
13.1.3.1(a)	Jheri Concrete faced Rock fill dam	9
13.1.3.1(b)	Jheri Non over flow Section	19
13.1.3.1(c)	Jheri Over flow Section	26
13.1.3.1(d)	Jheri dam gates	34
13.1.3.2(a)	Paikhed Concrete faced Rock fill dam	35
13.1.3.2 (b)	Paikhed Non over flow Section	45
13.1.3.2(c)	Paikhed Over flow Section	53
13.1.3.2(d)	Paikhed dam gates	61
13.1.3.2(e)	Paikhed Barrage	62
13.1.3.2(f)	Paikhed Head Regulator	66
13.1.3.2(g)	Paikhed Barrage and Head Regulator gate	69
13.1.3.3(a)	Chasmandva Concrete faced Rock fill dam	70
13.1.3.3 (b)	Chasmandva Non over flow Section	80
13.1.3.3(c)	Chasmandva Over flow Section	86
13.1.3.3(d)	Chasmandva dam gates	93
13.1.3.3(e)	Chasmandva Barrage	95
13.1.3.3(f)	Chasmandva Head Regulator	99
13.1.3.3(g)	Chasmandva Barrage and Head Regulator gate	102
13.1.3.4(a)	Chikkar Concrete faced Rock fill dam	103
13.1.3.4(b)	Chikkar Non over flow Section	114

Annexure No.	Title	Page No.
13.1.3.4(c)	Chikkar Over flow Section	121
13.1.3.4(d)	Chikkar dam gates	129
13.1.3.5(a)	Dabdar Concrete faced Rock fill dam	130
13.1.3.5(b)	Dabdar Non over flow Section	140
13.1.3.5(c)	Dabdar Over flow Section	148
13.1.3.5(d)	Dabdar dam gates	156
13.1.3.6(a)	Kelwan Concrete faced Rock fill dam	157
13.1.3.6(b)	Kelwan Non over flow Section	169
13.1.3.6(c)	Kelwan Over flow Section	177
13.1.3.6(d)	Kelwan dam gates	185
13.1.4	K - Buildings	186
13.1.5	M - Plantation	192
13.1.6	O - Miscellaneous	193
13.1.7	P - Maintenance	196
13.1.8	R - Communications	197
13.1.9	X - Environment & Ecology	198
13.2	General Abstract of Cost Unit-II: Canal System	206
13.2.1	B-Land	207
13.2.2	C - Works Abstract of cost of Tunnels	208
13.2.2.1 (a)	Cost of Tunnels	209
13.2.2.1 (b)	Cost of Tunnel gates	220
13.2.3	D-Regulators	221
13.2.4	E-Falls	225
13.2.5	F-Cross drainage structures	226
13.2.5.1	Aqueduct	227
13.2.5.2	Syphon aqueduct	230
13.2.5.3	Super passages	232
13.2.5.4	Canal syphon	235
13.2.5.5	Culverts	237
13.2.6	G – Bridges	238
13.2.7	H – Escapes	243
13.2.8	K – Buildings	244
13.2.9	L-Earthwork & Lining	249
13.2.9 (a)	Par-Tapi Reach including Feeder canals	250
13.2.9 (b)	Tapi-Narmada Reach	254
13.2.10	M-Plantation	258
13.2.11	O-Miscellaneous	259
13.2.12	P-Maintenance	261
13.2.13	R-Communications	262

Annexure No.	Title	Page No.
13.2.14	U-Distributaries/Minors	263
	V-Field channels & Water courses	
13.2.15	W-Drainage	264
13.2.16	X-Environment & Ecology	265
13.3	General Abstract of cost of Unit-III: Power	267
13.3.1	J – Abstract of Power Plant Civil works	268
13.3.1(a)	Paikhed dam toe power house	269
13.3.1(b)	Paikhed dam toe power house gate	280
13.3.1(c)	Chasmandva dam toe power house	281
13.3.1(d)	Chasmandva dam toe power house gate	289
13.3.1(e)	Chikkar dam toe power house	290
13.3.1(f)	Chikkar dam toe power house gate	297
13.3.1(g)	Dabdar dam toe power house	298
13.3.1(h)	Dabdar dam toe power house gate	306
13.3.1(i)	Kelwan dam toe power house	307
13.3.1(j)	Kelwan dam toe power house gate & Feeder canal gate	315
13.3.1(k)	Kelwan Feeder canal Power house	316
13.3.2	P – Maintenance	323
13.3.3	S – Abstract of Electro-mechanical works	324
13.3.3(a)	Paikhed dam toe power house	325
13.3.3(b)	Chasmandva dam toe power house	327
13.3.3(c)	Chikkar dam toe power house	330
13.3.3(d)	Dabdar dam toe power house	333
13.3.3(e)	Kelwan dam toe power house	336
13.3.3(f)	Kelwan Feeder canal Power house	339
13.4	General Abstract of cost of Unit-IV: Command area development	342
13.5	Calculation of B.C.Ratio	343
13.6	Calculation of I.R.R	344
13.7.1 (a)	Quantity estimate of Jheri dam (CFRD)	345
13.7.1 (b)	Quantity estimate of Jheri dam (NOF)	359
13.7.1 (c)	Quantity estimate of Jheri dam (OF)	365
13.7.2 (a)	Quantity estimate of Paikhed dam (CFRD)	372
13.7.2 (b)	Quantity estimate of Paikhed dam (NOF)	387
13.7.2 (c)	Quantity estimate of Paikhed dam (OF)	394
13.7.2 (d)	Quantity estimate of Paikhed Barrage	402
13.7.3 (a)	Quantity estimate of Chasmandva dam (CFRD)	407
13.7.3 (b)	Quantity estimate of Chasmandva dam (NOF)	424

Annexure No.	Title	Page No.
13.7.3 (c)	Quantity estimate of Chasmandva dam (OF)	431
13.7.3 (d)	Quantity estimate of Chasmandva Barrage	438
13.7.4 (a)	Quantity estimate of Chikkar dam (CFRD)	443
13.7.4 (b)	Quantity estimate of Chikkar dam (NOF)	458
13.7.4 (c)	Quantity estimate of Chikkar dam (OF)	465
13.7.5 (a)	Quantity estimate of Dabdar dam (CFRD)	473
13.7.5 (b)	Quantity estimate of Dabdar dam (NOF)	486
13.7.5 (c)	Quantity estimate of Dabdar dam (OF)	493
13.7.6 (a)	Quantity estimate of Kelwan dam (CFRD)	501
13.7.6 (b)	Quantity estimate of Kelwan dam (NOF)	515
13.7.6 (c)	Quantity estimate of Kelwan dam (OF)	523
13.8.1 (a)	Quantity estimate of Jheri-Paikhed tunnel	530
13.8.1 (b)	Quantity estimate of Par-Tapi reach and Feeder Canal	535
13.8.1 (c)	Quantity estimate of Tapi-Narmada reach Canal	634
13.8.1 (d)	Abstract of quantity of Canal lining	726
13.9.1 (a)	Quantity estimate of Paikhed dam toe Power house	727
13.9.1 (b)	Quantity estimate of Chasmandvar dam toe Power house	738
13.9.1 (c)	Quantity estimate of Chikkar dam toe Power house	747
13.9.1 (d)	Quantity estimate of Dabdar dam toe Power house	755
13.9.1 (e)	Quantity estimate of Kelwan dam toe Power house	764
13.9.1 (f)	Quantity estimate of Kelwan feeder canal Power house	772

Volume – VI (B)
Appendices - Cost Estimate

Annexure No.	Title	Page No.
13.10	Cost of Material, Hire Charges and Labour Charges for Rate Analysis	1
13.10.1	Rate Analysis for Dam	7

13.10.2	Rate Analysis for Tunnel	247
13.10.3	Rate Analysis for Power House	364
13.10.4	Quantities and Cost of U –Distributaries and V- Water courses	463
13.10.5	Benefits from pre and post project scenario	475

Volume – VII
Drawings - Surveys and Investigations

Plate No.	Title	Drawing No.
1.1	Index map of PTN link project	NWDA/PTN/Link/ICV/2014/1
4.1	Longitudinal Section of Par River: 17.70 km u/s and 10.60 km d/s of Proposed Jheri Dam Site	NWDA/PTN/Link/ICV/2014/2
4.2	Longitudinal Section of Nar River: 18.45 km u/s and 5.55 km d/s of Proposed Paikhed Dam Site	NWDA/PTN/Link/ICV/2014/3
4.3	Longitudinal Section of Nar River: 1.60 km u/s and 6.82 km d/s of Proposed Paikhed Weir Site	NWDA/PTN/Link/ICV/2014/4
4.4	Longitudinal Section of Tan River: 1.14 km u/s and 14.74 km d/s of Proposed Chasmandva Dam Site	NWDA/PTN/Link/ICV/2014/5
4.5	Longitudinal Section of Ambica River: 6.86 km u/s and 6.28 km d/s of Proposed Chikkar Dam Site	NWDA/PTN/Link/ ICV/2014/6
4.6	Longitudinal Section of Ambica River: 80 km towards Sea from Confluence with Khapri River Near Kalaamba Village	NWDA/PTN/Link/ ICV/2014/7
4.7	Longitudinal Section of Khapri River: 7.95 km u/s and 10.53 km d/s of Proposed Dabdar Dam Site	NWDA/PTN/Link/ ICV/2014/8
4.8	Longitudinal Section of Purna River: 14.25 km u/s and 5.19 km d/s of Proposed Kelwan Dam Site	NWDA/PTN/Link/ ICV/2014/9
4.9	Longitudinal Section of Purna River:	NWDA/PTN/Link/ ICV/2014/10

Plate No.	Title	Drawing No.
	85.80 km towards Sea from Waghi to Vyara Road Bridge	
4.10	Cross Section of Par River at Proposed Jheri Dam Site	NWDA/PTN/Link/ ICV/2014/11
4.11	Cross Section of Nar River (Tributary of Par River) at Proposed Paikhed Dam Site	NWDA/PTN/Link/ ICV/2014/12
4.12	Cross Section of Nar River (Tributary of Par River) at Proposed Paikhed Weir Site	NWDA/PTN/Link/ ICV/2014/13
4.13	Cross Section of Tan River (Tributary of Auranga River) at Proposed Chasmandva Dam Site	NWDA/PTN/Link/ ICV/2014/14
4.14	Cross Section of Tan River (Tributary of Auranga River) at Proposed Chasmandva Weir Site	NWDA/PTN/Link/ ICV/2014/15
4.15	Cross Section of Ambica River at Proposed Chikkar Dam Site	NWDA/PTN/Link/ ICV/2014/16
4.16	Cross Section of Khapri River (Tributary of Ambica River) at Proposed Dabdar Dam Site	NWDA/PTN/Link/ ICV/2014/17
4.17	Cross Section of Purna River at Proposed Kelwan Dam Site	NWDA/PTN/Link/ ICV/2014/18
4.18	Submergence Map of Jheri Reservoir (FR stage)	NWDA/PTN/Link/ ICV/2014/19
4.19	Submergence Map of Jheri Reservoir (DPR stage)	Prepared by BISAG
4.20	Submergence Map of Paikhed Reservoir (FR stage)	NWDA/PTN/Link/ ICV/2014/20
4.21	Submergence Map of Paikhed Reservoir (DPR stage)	Prepared by BISAG
4.22	Submergence Map of Chasmandva Reservoir (FR stage)	NWDA/PTN/Link/ ICV/2014/21
4.23	Submergence Map of Chasmandva (DPR stage)	Prepared by BISAG
4.24	Submergence Map of Chikkar Reservoir (FR stage)	NWDA/PTN/Link/ ICV/2014/22
4.25	Submergence Map of Chikkar Reservoir (DPR stage)	Prepared by BISAG
4.26	Submergence Map of Dabdar	NWDA/PTN/Link/ ICV/2014/23

Plate No.	Title	Drawing No.
	Reservoir (FR stage)	
4.27	Submergence Map of Dabdar Reservoir (DPR stage)	Prepared by BISAG
4.28	Submergence Map of Kelwan Reservoir (FR stage)	NWDA/PTN/Link/ ICV/2014/24
4.29	Submergence Map of Kelwan Reservoir (DPR stage)	Prepared by BISAG
4.30	Contour Plan of Jheri Dam Site Area	NWDA/PTN/Link/ ICV/2014/25
4.31	Contour Plan of Paikhed Dam Site Area	NWDA/PTN/Link/ ICV/2014/26
4.32	Contour Plan of Chasmandva Dam Site Area	NWDA/PTN/Link/ ICV/2014/27
4.33	Contour Plan of Chikkar Dam Site Area	NWDA/PTN/Link/ ICV/2014/28
4.34	Contour Plan of Dabdar Dam Site Area	NWDA/PTN/Link/ ICV/2014/29
4.35	Contour Plan of Kelwan Dam Site Area	NWDA/PTN/Link/ ICV/2014/30
4.36	Contour Plan of Kelwan Saddle dam Site Area	NWDA/PTN/Link/ ICV/2014/31
4.37	Contour Plan of Paikhed weir Site Area	NWDA/PTN/Link/ ICV/2014/32
4.38	Contour Plan of Chasmandva weir Site Area	NWDA/PTN/Link/ ICV/2014/33
4.39	Indicative Map Showing Plant and Colony Layout	NWDA/PTN/Link/ ICV/2014/34
4.40	Command Area Map of Par-Tapi-Narmada Link Project (Sheet 1 of 5)	NWDA/PTN/Link/ ICV/2014/35
4.40	Command Area Map of Par-Tapi-Narmada Link Project (Sheet 2 of 5)	NWDA/PTN/Link/ ICV/2014/36
4.40	Command Area Map of Par-Tapi-Narmada Link Project (Sheet 3 of 5)	NWDA/PTN/Link/ ICV/2014/37
4.40	Command Area Map of Par-Tapi-Narmada Link Project (Sheet 4 of 5)	NWDA/PTN/Link/ ICV/2014/38
4.40	Command Area Map of Par-Tapi-Narmada Link Project (Sheet 5 of 5)	NWDA/PTN/Link/ ICV/2014/39
4.41	Contour Plan of Sample Command Area Near Mandavi Village (Tapi-Narmada Reach)	NWDA/PTN/Link/ ICV/2014/40

Plate No.	Title	Drawing No.
4.42	Contour Plan of Sample Command Area Near Wankal Village (Tapi-Narmada Reach)	NWDA/PTN/Link/ ICV/2014/41
4.43	Contour Plan of Sample Command Area in Valiya Taluka (Tapi-Narmada Reach)	NWDA/PTN/Link/ ICV/2014/42
4.44	Map Showing Communication Network in the Project Area	NWDA/PTN/Link/ ICV/2014/43
4.45	Soil Map of Enroute Command Area of Par-Tapi-Narmada Link Project	NWDA/PTN/Link/ ICV/2014/44
4.46	Geological Plan of Jheri Dam Site	GSI Drawing
4.47	Geological Plan of Chasmandva Dam Site from RD 0 to 1000 m (Sheet 1 of 3)	GSI Drawing
4.47	Geological Plan of Chasmandava Dam Site from RD 1000 to 1900 m (Sheet 2 of 3)	GSI Drawing
4.47	Geological Plan of Chasmandva Dam Site from RD 1900 to 3000 m (Sheet 3 of 3)	GSI Drawing
4.48	Geological Plan of Chikkar Dam Alignment between RD 0 to 740 m (Sheet 1 of 2)	GSI Drawing
4.48	Geological Plan of Chikkar Dam Alignment between RD 740 to 2048 m (Sheet 2 of 2)	GSI Drawing
4.49	Geological plan of Dabdar Dam Alignment between RD 0 to 600 m. (Sheet 1 of 2)	GSI Drawing
4.49	Geological plan of Dabdar Dam Alignment between RD 600 to 1268 m. (Sheet 2 of 2)	GSI Drawing
4.50	Geological Plan of Kelwan Dam Alignment between RD 0 to 800 m (Sheet 1 of 2)	GSI Drawing
4.50	Geological Plan of Kelwan Dam Alignment between RD 800 to 1378 m. (Sheet 2 of 2)	GSI Drawing
4.51	Geological Plan of Proposed Kelwan	GSI Drawing

Plate No.	Title	Drawing No.
	Saddle Dam	
4.52	Geological Section along the Downstream axis Y-Y' of Jheri dam site	GSI Drawing
4.53	Tentative Geological Section along the Proposed Chasmandva Dam Axis between RD 0 to 1320 m (left NOF) Earthen Dam (Sheet 1 of 3)	GSI Drawing
4.53	Tentative Geological Section along the Proposed Chasmandva Dam Axis between RD 1320 m to 2500 m (Sheet 2 of 3)	GSI Drawing
4.53	Tentative Geological Section of Right NOF along the Proposed Chasmandva Dam Axis from RD 2500 m to 3050 m (Sheet 3 of 3)	GSI Drawing
4.54	Geological Sections of Chikkar Dam (Sheet 1 of 2)	GSI Drawing
4.54	Detailed Geological Section along Proposed Chikkar Masonry Dam between RD 1090 m to 1485 m (Sheet 2 of 2)	GSI Drawing
4.55	Tentative Geological Sections of Dabdar Dam	GSI Drawing
4.56	Tentative Geological Sections of Kelwan Dam	GSI Drawing
4.57	Tentative Geological Section along the Proposed Kelwan Saddle Dam Alignment.	GSI Drawing
4.58	Location Plan of Borrow Area Pits of Jheri Dam Area	NWDA/PTN/Link/ ICV/2014/45
4.59	Location Plan of Borrow Area Pits of Paikhed Dam Area	NWDA/PTN/Link/ ICV/2014/46
4.60	Location Plan of Borrow Area Pits of Chasmandva Dam Area	NWDA/PTN/Link/ ICV/2014/47
4.61	Location Plan of Borrow Area Pits of Chikkar Dam Area	NWDA/PTN/Link/ ICV/2014/48
4.62	Location Plan of Borrow Area Pits of Dabdar Dam Area	NWDA/PTN/Link/ ICV/2014/49
4.63	Location Plan of Borrow Area Pits of	NWDA/PTN/Link/ ICV/2014/50

Plate No.	Title	Drawing No.
	Kelwan Dam Area	
5.1	Par Basin Map	NWDA/PTN/Link/ ICV/2014/51
5.2	Auranga Basin Map	NWDA/PTN/Link/ ICV/2014/52
5.3	Ambica Basin Map	NWDA/PTN/Link/ ICV/2014/53
5.4	Purna Basin Map	NWDA/PTN/Link/ ICV/2014/54

Drawings-Report on Preliminary Geotechnical Investigations carried out by Geological
Survey of India, Jaipur

Plate No.	Title
A-1	Photo-geological Lineament Map of Dabdar Dam Site, the Dangs, Gujarat
A-2	Photo-geological Lineament Map of Chikkar Dam Site, the Dangs, Gujarat
A-3	Photo-geological Lineament Map of Kelwan Dam Site, the Dangs, Gujarat
A-4	Photo-geological Lineament Map of Chasmandva Dam Site, Valsad District, Gujarat
A-5	Photo-geological Lineament Map of Mohankavchali Dam Site, Valsad District, Gujarat
A-6	Photo-geological Lineament Map of Paikhed Dam Site, Valsad District, Gujarat
A-7	Photo-geological Lineament Map of Jheri Dam Site, Nashik District, Maharashtra
I	Bedrock Section along Dam and Energy Dissipation Axes along with the Location of Geophysical Observation Points and Magnetic Response (V.F), Dabdar Dam Site, District the Dangs, Gujarat
B-IA	Typical T-D Plot & VES Curves, Dabdar Dam Site, District the Dangs, Gujarat
B-II	Bedrock Section along Dam and Energy Dissipation Axes along with the Location of Geophysical Observation Points and Magnetic Response (V.F), Kelwan Dam Site, District the Dangs, Gujarat
B-IIA	Bedrock Section along Dam and Energy Dissipation Axes along with the Location of Geophysical Observation Points and Magnetic Response (V.F), Kelwan Saddle Dam Site, District the Dangs, Gujarat
B-II B	Typical T-D Plot & VES Curves, Kelwan Dam Site, District the Dangs, Gujarat

Plate No.	Title
B-III	Bedrock Section along Dam and Energy Dissipation Axes along with the Location of Geophysical Observation Points and Magnetic Response (V.F), Chikkar Dam Site, District the Dangs, Gujarat
B-III A	Typical T-D Plot & VES Curves, Chikkar Dam Site, District the Dangs, Gujarat
B-IV	Bedrock Section along Dam and Energy Dissipation Axes along with the Location of Geophysical Observation Points and Magnetic Response (V.F), Chasmandva Dam Site, District Valsad, Gujarat
B-IV A	Typical T-D Plot & VES Curves, Chasmandva Dam Site, District Valsad, Gujarat
B-V	Bedrock Section along Dam and Energy Dissipation Axes along with the Location of Geophysical Observation Points and Magnetic Response (V.F), Jheri Dam Site, District Nashik, Maharashtra
B-V A	Typical T-D Plot & VES Curves, Jheri Dam Site, District Nashik, Maharashtra
C-I	Geological Plan of Chikkar Dam Alignment between RD 740 to 2048 m (Enclosed as Plate No.4.48 Sheet 2 of 2) of this Drawing Volume)
C-II	Geological Plan of Chikkar Dam Alignment between RD 0 to 740 m (Enclosed as Plate No.4.48 Sheet 1 of 2 of this Drawing Volume)
C-III	Tentative Geological Section along the Proposed Chikkar Masonry Dam Alignment (C-D) between RD 1090 m to 1485 m (Enclosed as Plate No.4.54 Sheet 2 of 2 of this Drawing Volume)
C-IV	Tentative Geological Section along Proposed Chikkar Earthen Dam Alignment (B-C) between RD 340 m to 1090 m (Enclosed as Plate No.4.54 Sheet 1 of 2 of this Drawing Volume)
C-V	Tentative Geological Section along Proposed Chikkar Earthen Dam Alignment (A-B) between RD 0 m to 340 m (Enclosed as Plate No.4.54 Sheet 1 of 2 of this Drawing Volume)
C-VI	Tentative Geological Section along Proposed Chikkar Earthen Dam Alignment (C-D) between RD 1485 m to 2048 m (Enclosed as Plate No.4.54 Sheet 1 of 2 of this Drawing Volume)
C-VII	Tentative Geological Section along Left Bank of the River

Plate No.	Title
	Ambica Through Proposed Drill Hole at RD 1200 m (Enclosed as Plate No.4.54 Sheet 1 of 2 of this Drawing Volume)
C-VIII	Tentative Geological Section along Right Bank of the River Ambica Through Proposed Drill Hole at RD 1440 m (Enclosed as Plate No.4.54 Sheet 1 of 2 of this Drawing Volume)
C-IX	Tentative Geological Section along the River Ambica Through Drill Hole CKR-1 and Proposed Drill Hole No. CKR-2 (Enclosed as Plate No.4.54 Sheet 1 of 2 of this Drawing Volume)
C-X	Geological Log of Bore Hole No. CKR-1 from 0.00 m to 32.74 m
C-XI	Geological Log of Bore Hole No. CKR-1 from 32.74 m to 54.86 m
C-XII	Geological Log of the Trial Pits
C-XIII	Geological plan of Dabdar Dam Alignment District the Dangs, Gujarat (Enclosed as Plate No.4.49 Two Parts / Sheets of this Drawing Volume)
C-XIV	Section along the Proposed Dabdar Masonry Dam between RD 650 m and 980 m (Enclosed as Plate No.4.55 of this Drawing Volume)
C-XV	Section along the Proposed Dabdar Earth Dam between RD 0.00 m and 650 m (Enclosed as Plate No.4.55 of this Drawing Volume)
C-XVI	Section along the Proposed Dabdar Earth Dam between RD 980 m and 1300 m (Enclosed as Plate No.4.55 of this Drawing Volume)
C-XVII	Section along the Left Bank Through Bore Hole No. DBR-4 RD 689.393 m (Enclosed as Plate No.4.55 of this Drawing Volume)
C-XVIII	Section along the Right Bank Through Bore Hole No. DBR-2 RD 976.401 m (Enclosed as Plate No.4.55 of this Drawing Volume)
C-XIX	Section Across the Dam Alignment Through Bore Hole No. DBR-1 and 3 and River (Enclosed as Plate No.4.55 of this Drawing Volume)
C-XX	Geological Log of Bore Hole No. DBR-1
C-XXI	Geological Log of Bore Hole No. DBR-2
C-XXII	Geological Log of Bore Hole No. DBR-3
C-XXIII	Geological Log of Bore Hole No. DBR-4

Plate No.	Title
C-XXIV	Geological Log of the Trial Pits
C-XXV	Geological Plan of Kelwan Dam Alignment District the Dangs, Gujarat (Enclosed as Plate No.4.50 Two Parts/Sheets of this Drawing Volume)
C-XXVI	Tentative Geological Section along the Proposed Kelwan Masonry Dam Alignment Between RD 215 m and 552 m (Enclosed as Plate No.4.56 of this Drawing Volume)
C-XXVII	Tentative Geological Section along the Proposed Kelwan Earthen Dam Alignment Between RD 0.00 m and 215 m (Enclosed as Plate No.4.56 of this Drawing Volume)
C-XXVIII	Tentative Geological Section along the Proposed Kelwan Earthen Dam Alignment Between RD 552 m and 1388 m (Enclosed as Plate No.4.56 of this Drawing Volume)
C-XXIX	Tentative Geological Section along the Kelwan Dam Alignment at RD 205 m along Left Bank of Purna River (Enclosed as Plate No.4.56 of this Drawing Volume)
C-XXX	Tentative Geological Section across the Kelwan Dam Alignment at RD 550 m along Right Bank of Purna River (Enclosed as Plate No.4.56 of this Drawing Volume)
C-XXXI	Tentative Geological Section across the Kelwan Dam Alignment at RD 500 m along the Purna River (Enclosed as Plate No.4.56 of this Drawing Volume)
C-XXXII	Geological Log of the Trial Pits
C-XXXIII	Geological Plan of the Proposed Kelwan Saddle Dam, District the Dangs, Gujarat (Enclosed as Plate No.4.51 of this Drawing Volume)
C-XXXIV	Tentative Geological Section along the Kelwan Saddle Dam ,(Enclosed as Plate No.4.57 of this Drawing Volume)
C-XXXV	Geological Plan of Chasmandva Dam Site, District Valsad, from RD 0.00 m to 1000 m (Enclosed as Plate No.4.47 Sheet 1 of 3 of this Drawing Volume)
C-XXXVI	Geological Plan of Chasmandva Dam Site, District Valsad, from RD 1000 m to 1900 m (Enclosed as Plate No.4.47 Sheet 2 of 3 of this Drawing Volume)
C-XXXVII	Geological Plan of Chasmandva Dam Site, District Valsad, from RD 1900 m to 3000 m (Enclosed as Plate No.4.47 Sheet 3 of 3 of this Drawing Volume)
C-XXXVIII	Tentative Geological Section along the Proposed Chasmandva Dam Axis between RD 0.00 m to 1320 m (left NOF) Earthen Dam (Enclosed as Plate No.4.53 Sheet 1 of 3 of this Drawing Volume)

Plate No.	Title
C-XXXIX	Tentative Geological Section along the Proposed Chasmandva Dam Axis between RD 1320 m to 2500 m (Enclosed as Plate No.4.53 Sheet 2 of 3 of this Drawing Volume)
C-XL	Tentative Geological Section of Right NOF along the Proposed Chasmandva Dam Axis from RD 2500 m to 3050 m (Enclosed as Plate No.4.53 Sheet 3 of 3 of this Drawing Volume)
C-XLI	Geological Plan of Jheri dam site, District Nashik, Maharashtra (Enclosed as Plate No.4.46 of this Drawing Volume)
C-XLII	Geological Section along the Downstream axis Y-Y' of Jheri dam site (Enclosed as Plate No.4.52 of this Drawing Volume)
C-XLIII	Geological Log of Bore Hole BH-1 at Jheri Dam Site
C-XLIV	Geological Log of Bore Hole BH-2 at Jheri Dam Site
C-XLV	Geological Log of Bore Hole BH-3 at Jheri Dam Site
C-XLVI	Geological Log of Bore Hole BH-4 at Jheri Dam Site

Note: Text and Appendices of Report on Preliminary Geotechnical Investigations carried Out by Geological Survey of India, Western Region, Jaipur is enclosed as Appendix – 4.2 in Volume-III: Appendices- Survey Investigations.

Volume – VIII (A)
Drawings - Design Aspects

Plate No.	Description	CWC Drawing No.
1. 1	Index Map of Par-Tapi-Narmada Link Project (NWDA/PTN Link/ICV/2015/1)	-
6. 1	Plinth Foundation Treatment Details of Concrete Faced Rockfill Dam of Jheri Dam	PTNL-5900-P-1042
6. 2	Layout Plan of Concrete Faced Rockfill Dam of Jheri Dam	PTNL-5900-P-1036
6. 3	Section at A-A of Concrete Faced Rockfill Dam of Jheri Dam	PTNL-5900-P-1037
6. 4	Section at B-B of Concrete Faced Rockfill Dam of Jheri Dam	PTNL-5900-P-1038
6. 5	Joint Details of Concrete Faced Rockfill Dam of Jheri Dam	PTNL-5900-P-1039
6. 6	Plan of Interface Wall of Concrete Faced Rockfill Dam of Jheri Dam	PTNL-5900-P-1040
6. 7	Sectional Details of Interface Wall of Concrete Faced Rockfill Dam of Jheri Dam	PTNL-5900-P-1041
6. 8	Layout Plan of Jheri Dam	PTNL-5900-P-3041
6. 9	Maximum Non Over Flow (NOF) Section (Right Side) of Jheri Dam	PTNL-5900-P-3049
6. 10	Maximum Non over flow (NOF) Section (Left Side) of Jheri Dam	PTNL-5900-P-3052
6. 11	Zoning of Materials for Non Over Flow (NOF) Section (Right Side) of Jheri Dam.	PTNL-5900-P-3051
6. 12	Zoning of Materials for Non Over Flow (NOF) Section (Left Side) of Jheri Dam	PTNL-5900-P-3054
6. 13	Water Stop Details for Maximum Non Over Flow (NOF) Section (Right Side) of Jheri Dam	PTNL-5900-P-3050
6. 14	Water Stop Details for Maximum Non Over Flow (NOF) Section (Left Side) of Jheri Dam	PTNL-5900-P-3053
6. 15	Maximum Over Flow (OF) Section of Jheri	PTNL-5900-P-

Plate No.	Description	CWC Drawing No.
	Dam	3046
6. 16	Zoning of Materials for Maximum Over Flow (OF) Section of Jheri Dam	PTNL-5900-P-3048
6. 17	Water Stop Details for Maximum Over Flow (OF) Section of Jheri Dam	PTNL-5900-P-3047
6. 18	Typical Details of Consolidation Grouting in Over Flow (OF) Portion of Jheri Dam	PTNL-5900-P-3045
6. 19	Spillway Plan of Jheri Dam	PTNL-5900-P-3043
6. 20	Spillway Elevation of Jheri Dam	PTNL-5900-P-3044
6. 21	Longitudinal Section of Chute Spillway of Jheri Dam	PTNL-5900-P-3042
6. 22	Chute Channel and Cross Section at A-A of Jheri Dam	PTNL-5900-P-3055
6. 23	General Installation of Spillway Radial Gate (15000mmx12000mm) of Jheri Dam	PTNL-5900-JHD-1501
6. 24	General Installation of Spillway Stoplogs (15000mmx12600mm) of Jheri Dam	PTNL-5900-JHD-1502
6. 25	Plinth Foundation Treatment of Concrete Faced Rockfill Dam of Paikhed Dam	PTNL-5900-P-1028
6. 26	Layout Plan of Concrete Faced Rockfill Dam of Paikhed Dam	PTNL-5900-P-1022
6. 27	Section at A-A of Concrete Faced Rockfill Dam of Paikhed Dam	PTNL-5900-P-1023
6. 28	Section at B-B of Concrete Faced Rockfill Dam of Paikhed Dam	PTNL-5900-P-1024
6. 29	Joint Details of Concrete Faced Rockfill Dam of Paikhed Dam	PTNL-5900-P-1025
6. 30	Plan of Interface Wall of Concrete Faced Rockfill Dam of Paikhed Dam	PTNL-5900-P-1026
6. 31	Sectional Details of Interface Wall of Concrete Faced Rockfill Dam of Paikhed Dam	PTNL-5900-P-1027
6. 32	Layout Plan of Paikhed Dam	PTNL-5900-P-3001
6. 33	Maximum Non Over Flow (NOF) Section (Right Side) of Paikhed Dam	PTNL-5900-P-3011
6. 34	Maximum Non Over Flow (NOF) Section Power Intake Block of Paikhed Dam	PTNL-5900-P-3009
6. 35	Zoning of Materials for Non Over Flow (NOF)	PTNL-5900-P-

Plate No.	Description	CWC Drawing No.
	section of Paikhed Dam	3013
6. 36	Zoning of Materials for Non Over Flow (NOF) Section- Power Intake Block of Paikhed Dam	PTNL-5900-P-3010
6. 37	Water Stop Details for Non Over Flow (NOF) Section of Paikhed Dam	PTNL-5900-P-3012
6. 38	Maximum Over Flow (OF) Section of Paikhed Dam	PTNL-5900-P-3006
6. 39	Zoning of Materials for Maximum Over Flow (OF) Section of Paikhed Dam	PTNL-5900-P-3008
6. 40	Water Stop Details for Maximum Over Flow (OF) Section of Paikhed Dam	PTNL-5900-P-3007
6. 41	Typical Details of Consolidation Grouting in Over Flow (OF) Portion of Paikhed Dam	PTNL-5900-P-3004
6. 42	Spillway Plan of Paikhed Dam	PTNL-5900-P-3003
6. 43	Spillway Elevation of Paikhed Dam	PTNL-5900-P-3005
6. 44	Longitudinal Section of Chute Spillway of Paikhed Dam	PTNL-5900-P-3002
6. 45	Chute Channel and Cross Section at A-A of Paikhed Dam	PTNL-5900-P-3014
6. 46	Chute Channel and Cross Section at B-B of Paikhed Dam	PTNL-5900-P-3015
6. 47	General Installation of Spillway Radial Gate (15000mm X 12000 mm) of Paikhed Dam	PTNL-5900-PKD-1501
6. 48	General Installation of Spillway Stoplogs (15000mm X 12300mm) of Paikhed Dam	PTNL-5900-PKD-1502
6. 49	Plinth Foundation Treatment of Concrete Faced Rockfill Dam of Chasmandva Dam	PTNL-5900-P-1035
6. 50	Layout Plan of Concrete Faced Rockfill Dam of Chasmandva Dam	PTNL-5900-P-1029
6. 51	Section at A-A of Concrete Faced Rockfill Dam of Chasmandva Dam	PTNL-5900-P-1030
6. 52	Section at B-B of Concrete Faced Rockfill Dam of Chasmandva Dam	PTNL-5900-P-1031
6. 53	Joint Details of Concrete Faced Rockfill Dam of Chasmandva Dam	PTNL-5900-P-1032
6. 54	Plan of Interface Wall of Concrete Faced Rockfill Dam of Chasmandva Dam	PTNL-5900-P-1033
6. 55	Sectional Details of Interface Wall of Concrete	PTNL-5900-P-

Plate No.	Description	CWC Drawing No.
	Faced Rockfill Dam of Chasmandva Dam	1034
6. 56	Layout Plan of Chasmandva Dam	PTNL-5900-P-3021
6. 57	Maximum Non Over Flow (NOF) Section (Right Side) of Chasmandva Dam	PTNL-5900-P-3030
6. 58	Maximum Non Over Flow (NOF) Section (Left Side) of Chasmandva Dam	PTNL-5900-P-3033
6. 59	Zoning of Materials for Maximum Non Over Flow (NOF) Section (Right Side) of Chasmandva Dam	PTNL-5900-P-3031
6. 60	Water Stop Details for Non Over Flow (NOF) Section (Right side) of Chasmandva Dam	PTNL-5900-P-3032
6. 61	Maximum Over Flow (OF) Section of Chasmandva Dam	PTNL-5900-P-3026
6. 62	Zoning of Materials for Maximum Over Flow (OF) Section of Chasmandva Dam	PTNL-5900-P-3028
6. 63	Water Stop Details for Maximum Over Flow (OF) Section of Chasmandva Dam	PTNL-5900-P-3027
6. 64	Typical Details of Consolidation Grouting in Over Flow (OF) Portion of Chasmandva Dam	PTNL-5900-P-3025
6. 65	Spillway Plan of Chasmandva Dam	PTNL-5900-P-3024
6. 66	Spillway Elevation of Chasmandva Dam	PTNL-5900-P-3023
6. 67	Longitudinal Section of Chute Spillway of Chasmandva Dam	PTNL-5900-P-3022
6. 68	Chute Channel and Cross Section at A-A of Chasmandva Dam	PTNL-5900-P-3029
6. 69	General Installation of Spillway Radial Gate (12000 mm X 12000 mm) of Chasmandva Dam	PTNL-5900-CHVD-1501
6. 70	General Installation of Spillway Stoplogs (12000 mm X 12300 mm) of Chasmandva Dam	PTNL-5900-CHVD-1502
6. 71	Plinth Foundation Treatment of Concrete Faced Rockfill Dam of Chikkar Dam.	PTNL-5900-P-1049
6. 72	Layout Plan of Concrete Faced Rockfill Dam of Chikkar Dam	PTNL-5900-P-1043
6. 73	Section at A-A of Concrete Faced Rockfill Dam of Chikkar Dam	PTNL-5900-P-1044
6. 74	Section at B-B of Concrete Faced Rockfill Dam	PTNL-5900-P-

Plate No.	Description	CWC Drawing No.
	of Chikkar Dam	1045
6. 75	Joint Details of Concrete Faced Rockfill Dam of Chikkar Dam	PTNL-5900-P-1046
6. 76	Plan of Interface Wall of Concrete Faced Rockfill Dam of Chikkar Dam	PTNL-5900-P-1047
6. 77	Sectional Details of Interface Wall of Concrete Faced Rockfill Dam of Chikkar Dam	PTNL-5900-P-1048
6. 78	Layout Plan of Chikkar Dam	PTNL-5900-P-3061
6. 79	Maximum Non Over Flow (NOF) Section (Right Side) of Chikkar Dam	PTNL-5900-P-3072
6. 80	Maximum Non Over Flow (NOF) Section (Left Side) of Chikkar Dam	PTNL-5900-P-3069
6. 81	Zoning of Materials for Maximum Non Over Flow (NOF) Section (Right Side) of Chikkar Dam	PTNL-5900-P-3074
6. 82	Zoning of Materials for Maximum Non Over Flow (NOF) Section (Left Side) of Chikkar Dam	PTNL-5900-P-3071
6. 83	Water Stop Details for Non Over Flow (NOF) Section (Right Side) of Chikkar Dam	PTNL-5900-P-3073
6. 84	Water Stop Details for Non Over Flow (NOF) Section (Left Side) of Chikkar Dam	PTNL-5900-P-3070
6. 85	Maximum Over Flow (OF) Section of Chikkar Dam	PTNL-5900-P-3066
6. 86	Zoning of Materials for Maximum Over Flow (OF) Section of Chikkar Dam	PTNL-5900-P-3068
6. 87	Water Stop Details for Maximum Over Flow (OF) Section of Chikkar Dam	PTNL-5900-P-3067
6. 88	Typical Details of Consolidation Grouting in Over Flow (OF) Portion of Chikkar Dam	PTNL-5900-P-3065
6. 89	Spillway Plan of Chikkar Dam	PTNL-5900-P-3064
6. 90	Spillway Elevation of Chikkar Dam	PTNL-5900-P-3063
6. 91	Longitudinal Section of Chute Spillway of Chikkar Dam	PTNL-5900-P-3062
6. 92	Chute Channel and Cross Section at A-A of Chikkar Dam	PTNL-5900-P-3075
6. 93	General Installation of Spillway Radial Gate	PTNL-5900-

Plate No.	Description	CWC Drawing No.
	(15000 mm X 12000 mm) of Chikkar Dam	CKD-1501
6.94	General Installation of Spillway Stoplogs (15000 mm X 12900 mm) of Chikkar Dam	PTNL-5900-CKD-1502

Volume – VIII (B)
Drawings - Design Aspects

Plate No.	Description	CWC Drawing No.
1.1	Index Map of Par-Tapi-Narmada Link Project (NWDA/PTN Link/ICV/2015/1)	-
6.95	Plinth Foundation Treatment of Concrete Faced Rockfill Dam of Dabdar dam	PTNL-5900-P-1056
6.96	Layout Plan of Concrete Faced Rockfill Dam of Dabdar Dam	PTNL-5900-P-1050
6.97	Section at A-A of Concrete Faced Rockfill Dam of Dabdar Dam	PTNL-5900-P-1051
6.98	Section at B-B of Concrete Faced Rockfill Dam of Dabdar Dam	PTNL-5900-P-1052
6.99	Joint Details of Concrete Faced Rockfill Dam of Dabdar Dam	PTNL-5900-P-1053
6.100	Plan of Interface Wall of Concrete Faced Rockfill Dam of Dabdar Dam	PTNL-5900-P-1054
6.101	Sectional Details of Interface Wall of Concrete Faced Rockfill Dam of Dabdar Dam	PTNL-5900-P-1055
6.102	Layout Plan of Dabdar Dam	PTNL-5900-P-3081
6.103	Maximum Non Over Flow (NOF) Section (Right Side) of Dabdar Dam	PTNL-5900-P-3092
6.104	Maximum Non Over Flow (NOF) Section (Left side) of Dabdar Dam	PTNL-5900-P-3089
6.105	Zoning of Materials for Non Over Flow (NOF) Section (Right Side) of Dabdar Dam	PTNL-5900-P-3094
6.106	Zoning of Materials for Non Over Flow (NOF) Section (Left Side) of Dabdar Dam	PTNL-5900-P-3091
6.107	Water Stop Details for Non Over Flow (NOF) Section (Right Side) of Dabdar Dam	PTNL-5900-P-3093
6.108	Water Stop Details for Non Over Flow (NOF)	PTNL-5900-P-

Plate No.	Description	CWC Drawing No.
	Section (Left Side) of Dabdar Dam	3090
6.109	Maximum Over Flow (OF) Section of Dabdar Dam	PTNL-5900-P-3086
6.110	Zoning of Materials for Maximum Over Flow (OF) Section of Dabdar Dam	PTNL-5900-P-3088
6.111	Water Stop Details for Maximum Over Flow (OF) Section of Dabdar Dam	PTNL-5900-P-3087
6.112	Typical Details of Consolidation Grouting in Over Flow (OF) Portion of Dabdar Dam	PTNL-5900-P-3085
6.113	Spillway Plan of Dabdar Dam	PTNL-5900-P-3084
6.114	Spillway Elevation of Dabdar Dam	PTNL-5900-P-3083
6.115	Longitudinal Section of Chute Spillway of Dabdar Dam	PTNL-5900-P-3082
6.116	Chute Channel and Cross Section at A-A of Dabdar Dam	PTNL-5900-P-3095
6.117	General Installation of Spillway Radial Gate (15000 mm X 12000 mm) of Dabdar Dam	PTNL-5900-DBD-1501
6.118	General Installation of Spillway Stoplogs (15000 mm X 12600 mm) of Dabdar Dam	PTNL-5900-DBD-1502
6.119	Plinth Foundation Treatment Details of Concrete Faced Rockfill Dam of Kelwan Dam	PTNL-5900-P-1063
6.120	Layout Plan of Concrete Faced Rockfill Dam of Kelwan Dam	PTNL-5900-P-1057
6.121	Section at A-A of Concrete Faced Rockfill Dam of Kelwan Dam	PTNL-5900-P-1058
6.122	Section at B-B of Concrete Faced Rockfill Dam of Kelwan Dam	PTNL-5900-P-1059
6.123	Joint Details of Concrete Faced Rockfill Dam of Kelwan Dam	PTNL-5900-P-1060
6.124	Plan of Interface Wall of Concrete Faced Rockfill Dam of Kelwan Dam	PTNL-5900-P-1061
6.125	Sectional Details of Interface Wall of Concrete Faced Rockfill Dam of Kelwan Dam	PTNL-5900-P-1062
6.126	Layout plan of Kelwan dam	PTNL-5900-P-3101
6.127	Maximum Non Over flow (NOF) Section (Right Side) of Kelwan Dam	PTNL-5900-P-3109
6.128	Maximum Non Over flow (NOF) Section (Left	PTNL-5900-P-

Plate No.	Description	CWC Drawing No.
	Side) of Kelwan Dam	3112
6.129	Zoning of Materials for Non Over Flow (NOF) Section (Right Side) of Kelwan Dam	PTNL-5900-P-3111
6.130	Zoning of Materials for Non Over Flow (NOF) Section (Left Side) of Kelwan Dam	PTNL-5900-P-3114
6.131	Water Stop Details for Non Over flow (NOF) Section (Right Side) of Kelwan Dam	PTNL-5900-P-3110
6.132	Water Stop Details for Non Over flow (NOF) Section (Left Side) of Kelwan Dam	PTNL-5900-P-3113
6.133	Maximum Over flow (OF) Section of Kelwan Dam	PTNL-5900-P-3106
6.134	Zoning of Materials for Maximum Over flow (OF) Section of Kelwan Dam	PTNL-5900-P-3108
6.135	Water Stop details for Maximum Over flow (OF) Section of Kelwan Dam	PTNL-5900-P-3107
6.136	Typical Details of consolidations Grouting in Over flow (OF) Portion of Kelwan Dam	PTNL-5900-P-3105
6.137	Spillway Plan of Kelwan Dam	PTNL-5900-P-3104
6.138	Spillway Elevation of Kelwan Dam	PTNL-5900-P-3103
6.139	Longitudinal Section of Chute spillway of Kelwan Dam	PTNL-5900-P-3102
6.140	Chute Channel and Cross Section at A-A of Kelwan Dam	PTNL-5900-P-3115
6.141	General Installation of Spillway Radial Gate (15000mmX12000mm) of Kelwan Dam	PTNL-5900-KLD-1501
6.142	General Installation of Spillway Stoplogs (15000mmX12000mm) of Kelwan Dam	PTNL-5900-KLD-1502
6.143	General Layout Plan (Alternative Alignments) of Jheri-Paikhed Link Tunnel	PTNL-5900-DPR-1001
6.144	General Layout Plan (Final Alignment) of Jheri-Paikhed Link Tunnel	PTNL-5900-DPR-1002
6.145	L-section Along Jheri-Paikhed Link Tunnel	PTNL-5900-DPR-1003
6.146	Intake Details at Jheri of Jheri-Paikhed Link Tunnel	PTNL-5900-DPR-1004
6.147	Trash Rack Details (Metal Work) at Intake of Jheri-Paikhed Link Tunnel	PTNL-5900-DPR-1005
6.148	Typical Excavation and Rock Support Details	PTNL-5900-

Plate No.	Description	CWC Drawing No.
	(Horizontal Reach) of Jheri-Paikhed Link Tunnel	DPR-1006
6.149	Typical Concrete Lining and Grouting Details of Jheri-Paikhed Link Tunnel	PTNL-5900-DPR-1007
6.150	Construction Adit Portal Excavation Support Details of Jheri-Paikhed Link Tunnel	PTNL-5900-DPR-1008
6.151	Typical Excavation and Rock Support Details of Construction Adit (6 m x 6 m D-Shape) of Jheri-Paikhed Link Tunnel	PTNL-5900-DPR-1009
6.152	General Installation of Intake Service Gate (3000 mm X 3000 mm) at Jheri of Jheri-Paikhed Link Tunnel	PTNL-5900-JPLT-1501
6.153	General Installation of Intake Emergency Gate (3000 mm X 3000 mm) at Jheri of Jheri-Paikhed Link Tunnel	PTNL-5900-JPLT-1502
6.154	General Installation of Intake Service Gate (3000 mm X 3000 mm) at Paikhed of Jheri-Paikhed Link Tunnel	PTNL-5900-JPLT-1503
6.155	General Installation of Intake Emergency Gate (3000 mm X 3000 mm) at Paikhed of Jheri-Paikhed Link Tunnel	PTNL-5900-JPLT-1504
6.156	General Layout Plan (Alternative Alignments) of Power House at Paikhed Dam	PTNL-5900-DPR-2001
6.157	General Layout Plan (Final Alignment) of Power House at Paikhed Dam	PTNL-5900-DPR-2002
6.158	L-section of Water Conductor System and Power House at Paikhed Dam	PTNL-5900-DPR-2003
6.159	Plan and Section of Power Intake of Power House at Paikhed Dam	PTNL-5900-DPR-2004
6.160	Trash Rack Details (Metal Work) of Power Intake of Power House at Paikhed Dam	PTNL-5900-DPR-2005
6.161	Pressure Shaft (Typical Excavation on Rock Support Details) of Power House at Paikhed Dam	PTNL-5900-DPR-2006
6.162	Pressure Shaft (Typical Concrete Lining and Grouting Details) of Power House at Paikhed Dam	PTNL-5900-DPR-2007
6.163	Penstock / Pressure Shaft (Ferrule Details) of Power House at Paikhed Dam	PTNL-5900-DPR-2008
6.164	Penstock Shaft (Ferrule Details) of Power House at Paikhed Dam	PTNL-5900-DPR-2009

Plate No.	Description	CWC Drawing No.
6.165	Plan of Power House at Paikhed Dam	PTNL-5900-DPR-2010
6.166	Cross Section of Surface Power House at Paikhed Dam	PTNL-5900-DPR-2011
6.167	General Installation of Power Intake Service Gate (1800 mm X 2500 mm) at Paikhed Dam	PTNL-5900-PKPH-1501
6.168	General Installation of Draft Tube Gate (4020 mmX2300 mm) at Paikhed Dam	PTNL-5900-PKPH-1502
6.169	General Layout Plan (Alternative Alignments) of Power House at Chasmandva Dam	PTNL-5900-DPR-3001
6.170	General Layout Plan (Final Alignment) of Power House at Chasmandva Dam	PTNL-5900-DPR-3002
6.171	Layout Plan of Water Conductor System and Power House at Chasmandva Dam	PTNL-5900-DPR-3003
6.172	L-Section of Water Conductor System and Power House at Chasmandva Dam	PTNL-5900-DPR-3004
6.173	Plan and Section of Power Intake of Power House at Chasmandva Dam	PTNL-5900-DPR-3005
6.174	Trash Rack Details (Metal Work) of Power Intake of Power House at Chasmandva Dam	PTNL-5900-DPR-3006
6.175	Penstock (Details of Steel Liner) of Power House at Chasmandva Dam (Sheet 1 of 2)	PTNL-5900-DPR-3007
6.176	Penstock (Details of Steel Liner) of Power House at Chasmandva Dam (Sheet 2 of 2)	PTNL-5900-DPR-3008
6.177	Plan of Surface Power House at Elevation of 175.120 m of Chasmandva Dam	PTNL-5900-DPR-3009
6.178	Cross Section of Surface Power House at Chasmandva Dam	PTNL-5900-DPR-3010
6.179	L-Section Through Centre Line of Turbine of Surface Power House at Chasmandva Dam	PTNL-5900-DPR-3011
6.180	General Installation of Power Intake Service Gate (1420 mm X 1800 mm) at Chasmandva Dam	PTNL-5900-CHPH-1501
6.181	General Installation of Draft Tube Gate (3400 mm X 2340 mm) at Chasmandva Dam	PTNL-5900-CHPH-1502
6.182	General Layout Plan (Alternative Alignments) of Power House at Chikkar Dam	PTNL-5900-DPR-4001
6.183	General Layout Plan (Final Alignment) of Power House at Chikkar Dam	PTNL-5900-DPR-4002
6.184	L-section of Water Conductor System and Power	PTNL-5900-

Plate No.	Description	CWC Drawing No.
	House at Chikkar Dam	DPR-4003
6.185	Power Intake Details of Power House at Chikkar Dam	PTNL-5900-DPR-4004
6.186	Trash Rack Details (Metal Work) of Power Intake of Power House at Chikkar Dam	PTNL-5900-DPR-4005
6.187	Penstock (Details of Steel Liner) of Power House at Chikkar Dam (Sheet 1 of 2)	PTNL-5900-DPR-4006
6.188	Penstock (Details of Steel Liner) of Power House at Chikkar Dam (Sheet 2 of 2)	PTNL-5900-DPR-4007
6.189	Plan of Surface Power House at Elevation of 167.920 m of Chikkar Dam	PTNL-5900-DPR-4008
6.190	L-Section Through Centre Line of Turbine of Surface Power House at Chikkar Dam	PTNL-5900-DPR-4009
6.191	Cross Section of Power House at Chikkar Dam	PTNL-5900-DPR-4010
6.192	General Installation of Power Intake Service Gate (1420 mm X 1800 mm) at Chikkar Dam	PTNL-5900-CKPH-1501
6.193	General Installation of Draft Tube Gate (3400 mm X 2340 mm) at Chikkar Dam	PTNL-5900-CKPH-1502
6.194	General Layout Plan of Power House at Dabdar Dam	PTNL-5900-DPR-5001
6.195	L-section of Water Conductor System and Power House at Dabdar Dam	PTNL-5900-DPR-5002
6.196	Plan and Section of Power Intake of Power House at Dabdar Dam	PTNL-5900-DPR-5003
6.197	Trash Rack Details (Metal Work) of Power Intake of Power House at Dabdar Dam	PTNL-5900-DPR-5004
6.198	Penstock (Details of Steel Liner) of Power House at Dabdar Dam (Sheet 1 of 2)	PTNL-5900-DPR-5005
6.199	Penstock (Details of Steel Liner) of Power House at Dabdar Dam (Sheet 2 of 2)	PTNL-5900-DPR-5006
6.200	Plan of Power House at Elevation of 135.830 m of Dabdar Dam	PTNL-5900-DPR-5007
6.201	Cross Section of Surface Power House at Dabdar Dam	PTNL-5900-DPR-5008
6.202	L-Section Through Centre Line of Turbine of Surface Power House at Dabdar Dam	PTNL-5900-DPR-5009
6.203	General Installation of Power Intake Service Gate (2000 mm X 2500 mm) at Dabdar Dam	PTNL-5900-DBPH-1501
6.204	General Installation of Draft Tube Gate (5100	PTNL-5900-

Plate No.	Description	CWC Drawing No.
	mm X 2340 mm) at Dabdar Dam	DBPH-1502
6.205	General Layout Plan of Power House at Kelwan Dam	PTNL-5900-DPR-6001
6.206	L-section of Water Conductor System and Power House at Kelwan Dam	PTNL-5900-DPR-6002
6.207	Plan and Section of Power Intake of Power House at Kelwan Dam	PTNL-5900-DPR-6003
6.208	Trash Rack Details (Metal Work) of Power Intake of Power House at Kelwan Dam	PTNL-5900-DPR-6004
6.209	Penstock (Details of Steel Liner) of Power House at Kelwan Dam (Sheet 1 of 2)	PTNL-5900-DPR-6005
6.210	Penstock (Details of Steel Liner) of Power House at Kelwan Dam (Sheet 2 of 2)	PTNL-5900-DPR-6006
6.211	Plan of Power House at Elevation of 134.830 m of Kelwan Dam	PTNL-5900-DPR-6007
6.212	Cross Section of Power House at Kelwan Dam	PTNL-5900-DPR-6008
6.213	L-Section Through Centre Line of Turbine of Surface Power House at Kelwan Dam	PTNL-5900-DPR-6009
6.214	General Installation of Power Intake Service Gate (1800 mm X 2500 mm) at Kelwan Dam	PTNL-5900-KEPH-1501
6.215	General Installation of Draft Tube Gate (4020 mm X 2300 mm) at Kelwan Dam	PTNL-5900-KEPH-1502
6.216	General Layout Plan of Power House at Kelwan Feeder Canal	PTNL-5900-DPR-7001
6.217	L-section of Water Conductor System and Power House at Kelwan Feeder Canal	PTNL-5900-DPR-7002
6.218	Plan and Section of Power Intake of Power House at Kelwan Feeder Canal	PTNL-5900-DPR-7003
6.219	Trash Rack Details (Metal Work) of Power Intake of Power House at Kelwan Feeder Canal	PTNL-5900-DPR-7004
6.220	Penstock Details of Steel Liner (Details of Ferrule) of Power House at Kelwan Feeder Canal	PTNL-5900-DPR-7005
6.221	Penstock Details of Steel Liner (Details of Ferrule) of Power House at Kelwan Feeder Canal	PTNL-5900-DPR-7006
6.222	Plan of Power House at Elevation of 118.180 m of Kelwan Feeder Canal	PTNL-5900-DPR-7007
6.223	Cross Section of Power House at Kelwan Feeder Canal	PTNL-5900-DPR-7008
6.224	Power House Roof Truss Details at Kelwan	PTNL-5900-

Plate No.	Description	CWC Drawing No.
	Feeder Canal	DPR-7009
6.225	General Installation of Power Intake Service Gate (2000 mm X 2500 mm) at Kelwan Feeder Canal	PTNL-5900-KFCPH-1501
6.226	General Installation of Power Intake Emergency Gate (2000 mm X 2500 mm) at Kelwan Feeder Canal	PTNL-5900-KFCPH-1502
6.227	General Installation of Draft Tube Gate (2652 mm X 1500 mm) at Kelwan Feeder Canal	PTNL-5900-KFCPH-1503
6.228	General Layout Plan of Paikhed Barrage	PTNL-5900-P-2501
6.229	Detailed Layout Plan of Paikhed Barrage	PTNL-5900-P-2502
6.230	Longitudinal and Cross Section (Anchorage and Drainage Details) of Paikhed Barrage	PTNL-5900-P-2503
6.231	Stilling Basin Plan (Anchorage and Drainage Details) of Paikhed Barrage	PTNL-5900-P-2504
6.232	Head Regulator and Flared Out Walls of Paikhed Barrage	PTNL-5900-P-2505
6.233	General Installation of Spillway Radial Gate (15000 mm X 7000 mm) of Paikhed Barrage	PTNL-5900-PKB-1501
6.234	General Installation of Spillway Stop log (15000 mm X 9100 mm) of Paikhed Barrage	PTNL-5900-PKB-1502
6.235	General Installation of Head Regulator Service Gate (3000 mm X 3000 mm) of Paikhed Barrage	PTNL-5900-PKB-1503
6.236	General Installation of Stoplog (3000 mm X 3350 mm) for Head Regulator of Paikhed Barrage	PTNL-5900-PKB-1504
6.237	General Layout Plan of Chasmandva Barrage	PTNL-5900-P-2506
6.238	Detailed Layout Plan of Chasmandva Barrage	PTNL-5900-P-2507
6.239	Longitudinal and Cross Section (Anchorage and Drainage Details) of Chasmandva Barrage	PTNL-5900-P-2508
6.240	Stilling Basin Plan (Anchorage and Drainage Details) of Chasmandva Barrage	PTNL-5900-P-2509
6.241	Head Regulator and Flared Out Walls of Chasmandva Barrage	PTNL-5900-P-2510
6.242	General Installation of Spillway Gate (12000	PTNL-5900-

Plate No.	Description	CWC Drawing No.
	mm X 8000 mm) of Chasmandva Barrage	CHB-1501
6.243	General Installation of Spillway Stop log (12000 mm X 8250 mm) of Chasmandva Barrage	PTNL-5900-CHB-1502
6.244	General Installation of Head Regulator Service Gate (3000 mm X 1000 mm) of Chasmandva Barrage	PTNL-5900-CHB-1503
6.245	General Installation of Stoplog (3000 mm X 1200 mm) for Head Regulator of Chasmandva Barrage	PTNL-5900-CHB-1504

Volume – VIII (C)
Drawings - Design Aspects

Plate No.	Description	CWC Drawing No.
1. 1	Index Map of Par-Tapi-Narmada Link Project (NWDA/PTN Link/ICV/2015/1)	-
6.246	Canal Section(s) – At Different Reaches of Main Canals and Feeder Canals	PTNL-5900-P-2511
6.247	Canal Section(s) – Typical Details of Cutting and Filling	PTNL-5900-P-2512
6.248	Typical Details of Canal Lining	PTNL-5900-P-2513
6.249	Typical Details of Drainage Arrangement Under Canal Lining	PTNL-5900-P-2514
	Par-Tapi Reach	
6.250	Canal Alignment and Longitudinal Section from RD 0.00 to RD 3000 m	PTNL-5900-P-2515
6.251	Canal Alignment and Longitudinal Section from RD 3000 m to RD 6000 m	PTNL-5900-P-2516
6.252	Canal Alignment and Longitudinal Section from RD 6000 m to RD 9000 m	PTNL-5900-P-2517
6.253	Canal Alignment and Longitudinal Section from RD 9000 m to RD 12000 m	PTNL-5900-P-2518
6.254	Canal Alignment and Longitudinal Section from RD 12000 m to RD 15000 m	PTNL-5900-P-2519
6.255	Canal Alignment and Longitudinal Section from RD 15000 m to RD 18000 m	PTNL-5900-P-2520
6.256	Canal Alignment and Longitudinal Section from RD 18000 m to RD 21000 m	PTNL-5900-P-2521
6.257	Canal Alignment and Longitudinal Section from RD 21000 m to RD 24000 m	PTNL-5900-P-2522

Plate No.	Description	CWC Drawing No.
6.258	Canal Alignment and Longitudinal Section from RD 24000 m to RD 27000 m	PTNL-5900-P-2523
6.259	Canal Alignment and Longitudinal Section from RD 27000 m to RD 30000 m	PTNL-5900-P-2524
6.260	Canal Alignment and Longitudinal Section from RD 30000 m to RD 33000 m	PTNL-5900-P-2525
6.261	Canal Alignment and Longitudinal Section from RD 33000 m to RD 36000 m	PTNL-5900-P-2526
6.262	Canal Alignment and Longitudinal Section from RD 36000 m to RD 39000 m	PTNL-5900-P-2527
6.263	Canal Alignment and Longitudinal Section from RD 39000 m to RD 42000 m	PTNL-5900-P-2528
6.264	Canal Alignment and Longitudinal Section from RD 42000 m to RD 45000 m	PTNL-5900-P-2529
6.265	Canal Alignment and Longitudinal Section from RD 45000 m to RD 48000 m	PTNL-5900-P-2530
6.266	Canal Alignment and Longitudinal Section from RD 48000 m to RD 51000 m	PTNL-5900-P-2531
6.267	Canal Alignment and Longitudinal Section from RD 51000 m to RD 54000 m	PTNL-5900-P-2532
6.268	Canal Alignment and Longitudinal Section from RD 54000 m to RD 57000 m	PTNL-5900-P-2533
6.269	Canal Alignment and Longitudinal Section from RD 57000 m to RD 60000 m	PTNL-5900-P-2534
6.270	Canal Alignment and Longitudinal Section from RD 60000 m to RD 63000 m	PTNL-5900-P-2535
6.271	Canal Alignment and Longitudinal Section from RD 63000 m to RD 66000 m	PTNL-5900-P-2536
6.272	Canal Alignment and Longitudinal Section from RD 66000 m to RD 69000 m	PTNL-5900-P-2537
6.273	Canal Alignment and Longitudinal Section from RD 69000 m to RD 72000 m	PTNL-5900-P-2538
6.274	Canal Alignment and Longitudinal Section from RD 72000 m to RD 75000 m	PTNL-5900-P-2539
6.275	Canal Alignment and Longitudinal Section from RD 75000 m to RD 78000 m	PTNL-5900-P-2540
6.276	Canal Alignment and Longitudinal Section from RD 78000 m to RD 81000 m	PTNL-5900-P-2541
6.277	Canal Alignment and Longitudinal Section from RD 81000 m to RD 84000 m	PTNL-5900-P-2542

Plate No.	Description	CWC Drawing No.
6.278	Canal Alignment and Longitudinal Section from RD 84000 m to RD 87000 m	PTNL-5900-P-2543
6.279	Canal Alignment and Longitudinal Section from RD 87000 m to RD 90000 m	PTNL-5900-P-2544
6.280	Canal Alignment and Longitudinal Section from RD 90000 m to RD 93000 m	PTNL-5900-P-2545
6.281	Canal Alignment and Longitudinal Section from RD 93000 m to RD 96000 m	PTNL-5900-P-2546
6.282	Canal Alignment and Longitudinal Section from RD 96000 m to RD 99000 m	PTNL-5900-P-2547
6.283	Canal Alignment and Longitudinal Section from RD 99000 m to RD 102000 m	PTNL-5900-P-2548
6.284	Canal Alignment and Longitudinal Section from RD 102000 m to RD 105000 m	PTNL-5900-P-2549
6.285	Canal Alignment and Longitudinal Section from RD 105000 m to RD 108000 m	PTNL-5900-P-2550
6.286	Canal Alignment and Longitudinal Section from RD 108000 m to RD 111000 m	PTNL-5900-P-2551
6.287	Canal Alignment and Longitudinal Section from RD 111000 m to RD 114000 m	PTNL-5900-P-2552
6.288	Canal Alignment and Longitudinal Section from RD 114000 m to RD 117000 m	PTNL-5900-P-2553
6.289	Canal Alignment and Longitudinal Section from RD 117000 m to RD 120000 m	PTNL-5900-P-2554
6.290	Canal Alignment and Longitudinal Section from RD 120000 m to RD 123000 m	PTNL-5900-P-2555
6.291	Canal Alignment and Longitudinal Section from RD 123000 m to RD 126000 m	PTNL-5900-P-2556
6.292	Canal Alignment and Longitudinal Section from RD 126000 m to RD 129000 m	PTNL-5900-P-2557
6.293	Canal Alignment and Longitudinal Section from RD 129000 m to RD 132000 m	PTNL-5900-P-2558
6.294	Canal Alignment and Longitudinal Section from RD 132000 m to RD 135000 m	PTNL-5900-P-2559
6.295	Canal Alignment and Longitudinal Section from RD 135000 m to RD 138000 m	PTNL-5900-P-2560
6.296	Canal Alignment and Longitudinal Section from RD 138000 m to RD 141000 m	PTNL-5900-P-2561
6.297	Canal Alignment and Longitudinal Section from RD 141000 m to RD 144000 m	PTNL-5900-P-2562

Plate No.	Description	CWC Drawing No.
6.298	Canal Alignment and Longitudinal Section from RD 144000 to RD 147000 m	PTNL-5900-P-2563
6.299	Canal Alignment and Longitudinal Section from RD 147000 m to RD 150000 m	PTNL-5900-P-2564
6.300	Canal Alignment and Longitudinal Section from RD 150000 m to RD 153000 m	PTNL-5900-P-2565
6.301	Canal Alignment and Longitudinal Section from RD 153000 m to RD 156000 m	PTNL-5900-P-2566
6.302	Canal Alignment and Longitudinal Section from RD 156000 m to RD 159000 m	PTNL-5900-P-2567
6.303	Canal Alignment and Longitudinal Section from RD 159000 m to RD 162000 m	PTNL-5900-P-2568
6.304	Canal Alignment and Longitudinal Section from RD 162000 m to RD 165000 m	PTNL-5900-P-2569
6.305	Canal Alignment and Longitudinal Section from RD 165000 m to RD 168000 m	PTNL-5900-P-2570
6.306	Canal Alignment and Longitudinal Section from RD 168000 m to RD 171000 m	PTNL-5900-P-2571
6.307	Canal Alignment and Longitudinal Section from RD 171000 m to RD 174000 m	PTNL-5900-P-2572
6.308	Canal Alignment and Longitudinal Section from RD 174000 m to RD 177360 m	PTNL-5900-P-2573
	Feeder Canals	
6.309	Canal Alignment and Longitudinal Section from RD 0.00 to RD 2859.91 m of Chasmandva Feeder Canal	PTNL-5900-P-2574
6.310	Canal Alignment and Longitudinal Section from RD 0.00 to RD 3000.00 m of Interconnecting Canal between Chikkar and Dabdar Reservoirs	PTNL-5900-P-2575
6.311	Canal Alignment and Longitudinal Section from RD 3000.00 m to RD 6000.00 m of Interconnecting Canal between Chikkar and Dabdar Reservoirs	PTNL-5900-P-2576
6.312	Canal Alignment and Longitudinal Section from RD 6000.00 m to RD 9000.00 m of Interconnecting Canal between Chikkar and Dabdar Reservoirs	PTNL-5900-P-2577
6.313	Canal Alignment and Longitudinal Section from RD 9000.00 m to RD 12000.00 m of Interconnecting Canal between Chikkar and	PTNL-5900-P-2578

Plate No.	Description	CWC Drawing No.
	Dabdar Reservoirs	
6.314	Canal Alignment and Longitudinal Section from RD 12000.00 m to RD 14341.97 m of Interconnecting Canal between Chikkar and Dabdar Reservoirs	PTNL-5900-P-2579
6.315	Canal Alignment and Longitudinal Section from RD 0.00 to RD 3100.00 m of Dabdar Feeder Canal	PTNL-5900-P-2580
6.316	Canal Alignment and Longitudinal Section from RD 3100.00 m to RD 6200.00 m of Dabdar Feeder Canal	PTNL-5900-P-2581
6.317	Canal Alignment and Longitudinal Section from RD 6200.00 m to RD 9300.00 m of Dabdar Feeder Canal	PTNL-5900-P-2582
6.318	Canal Alignment and Longitudinal Section from RD 9300.00 m to RD 12258.087 m of Dabdar Feeder Canal	PTNL-5900-P-2583
6.319	Canal Alignment and Longitudinal Section from RD 0.00 to RD 3100.00 m of Kelwan Feeder Canal	PTNL-5900-P-2584
6.320	Canal Alignment and Longitudinal Section from RD 3100.00 m to RD 6200.00 m of Kelwan Feeder Canal	PTNL-5900-P-2585
6.321	Canal Alignment and Longitudinal Section from RD 6200.00 m to RD 7615.69 m of Kelwan Feeder Canal	PTNL-5900-P-2586
	Tapi-Narmada Reach	
6.322	Canal Alignment and Longitudinal Section from RD 0.00 to RD 3000 m	PTNL-5900-P-2587
6.323	Canal Alignment and Longitudinal Section from RD 3000 m to RD 6000 m	PTNL-5900-P-2588
6.324	Canal Alignment and Longitudinal Section from RD 6000 m to RD 9000 m	PTNL-5900-P-2589
6.325	Canal Alignment and Longitudinal Section from RD 9000 m to RD 12000 m	PTNL-5900-P-2590
6.326	Canal Alignment and Longitudinal Section from RD 12000 m to RD 15000 m	PTNL-5900-P-2591
6.327	Canal Alignment and Longitudinal Section from RD 15000 m to RD 18000 m	PTNL-5900-P-2592
6.328	Canal Alignment and Longitudinal Section from	PTNL-5900-P-

Plate No.	Description	CWC Drawing No.
	RD 18000 m to RD 21000 m	2593
6.329	Canal Alignment and Longitudinal Section from RD 21000 m to RD 24000 m	PTNL-5900-P-2594
6.330	Canal Alignment and Longitudinal Section from RD 24000 m to RD 27000 m	PTNL-5900-P-2595
6.331	Canal Alignment and Longitudinal Section from RD 27000 m to RD 30000 m	PTNL-5900-P-2596
6.332	Canal Alignment and Longitudinal Section from RD 30000 m to RD 33000 m	PTNL-5900-P-2597
6.333	Canal Alignment and Longitudinal Section from RD 33000 m to RD 36000 m	PTNL-5900-P-2598
6.334	Canal Alignment and Longitudinal Section from RD 36000 m to RD 39000 m	PTNL-5900-P-2599
6.335	Canal Alignment and Longitudinal Section from RD 39000 m to RD 42000 m	PTNL-5900-P-2600
6.336	Canal Alignment and Longitudinal Section from RD 42000 m to RD 45000 m	PTNL-5900-P-2601
6.337	Canal Alignment and Longitudinal Section from RD 45000 m to RD 48000 m	PTNL-5900-P-2602
6.338	Canal Alignment and Longitudinal Section from RD 48000 m to RD 51000 m	PTNL-5900-P-2603
6.339	Canal Alignment and Longitudinal Section from RD 51000 m to RD 54000 m	PTNL-5900-P-2604
6.340	Canal Alignment and Longitudinal Section from RD 54000 m to RD 57000 m	PTNL-5900-P-2605
6.341	Canal Alignment and Longitudinal Section from RD 57000 m to RD 60000 m	PTNL-5900-P-2606
6.342	Canal Alignment and Longitudinal Section from RD 60000 m to RD 63000 m	PTNL-5900-P-2607
6.343	Canal Alignment and Longitudinal Section from RD 63000 m to RD 66000 m	PTNL-5900-P-2608
6.344	Canal Alignment and Longitudinal Section from RD 66000 m to RD 69000 m	PTNL-5900-P-2609
6.345	Canal Alignment and Longitudinal Section from RD 69000 m to RD 72000 m	PTNL-5900-P-2610
6.346	Canal Alignment and Longitudinal Section from RD 72000 m to RD 75000 m	PTNL-5900-P-2611
6.347	Canal Alignment and Longitudinal Section from RD 75000 m to RD 78000 m	PTNL-5900-P-2612
6.348	Canal Alignment and Longitudinal Section from	PTNL-5900-P-

Plate No.	Description	CWC Drawing No.
	RD 78000 m to RD 81000 m	2613
6.349	Canal Alignment and Longitudinal Section from RD 81000 m to RD 84000 m	PTNL-5900-P-2614
6.350	Canal Alignment and Longitudinal Section from RD 84000 m to RD 87000 m	PTNL-5900-P-2615
6.351	Canal Alignment and Longitudinal Section from RD 87000 m to RD 90000 m	PTNL-5900-P-2616
6.352	Canal Alignment and Longitudinal Section from RD 90000 m to RD 93000 m	PTNL-5900-P-2617
6.353	Canal Alignment and Longitudinal Section from RD 93000 m to RD 96000 m	PTNL-5900-P-2618
6.354	Canal Alignment and Longitudinal Section from RD 96000 m to RD 99000 m	PTNL-5900-P-2619
6.355	Canal Alignment and Longitudinal Section from RD 99000 m to RD 102000 m	PTNL-5900-P-2620
6.356	Canal Alignment and Longitudinal Section from RD 102000 m to RD 105000 m	PTNL-5900-P-2621
6.357	Canal Alignment and Longitudinal Section from RD 105000 m to RD 108000 m	PTNL-5900-P-2622
6.358	Canal Alignment and Longitudinal Section from RD 108000 m to RD 111000 m	PTNL-5900-P-2623
6.359	Canal Alignment and Longitudinal Section from RD 111000 m to RD 114000 m	PTNL-5900-P-2624
6.360	Canal Alignment and Longitudinal Section from RD 114000 m to RD 117000 m	PTNL-5900-P-2625
6.361	Canal Alignment and Longitudinal Section from RD 117000 m to RD 120000 m	PTNL-5900-P-2626
6.362	Canal Alignment and Longitudinal Section from RD 120000 m to RD 123000 m	PTNL-5900-P-2627
6.363	Canal Alignment and Longitudinal Section from RD 123000 m to RD 126000 m	PTNL-5900-P-2628
6.364	Canal Alignment and Longitudinal Section from RD 126000 m to RD 129000 m	PTNL-5900-P-2629
6.365	Canal Alignment and Longitudinal Section from RD 129000 m to RD 132000 m	PTNL-5900-P-2630
6.366	Canal Alignment and Longitudinal Section from RD 132000 m to RD 135000 m	PTNL-5900-P-2631
6.367	Canal Alignment and Longitudinal Section from RD 135000 m to RD 138000 m	PTNL-5900-P-2632
6.368	Canal Alignment and Longitudinal Section from	PTNL-5900-P-

Plate No.	Description	CWC Drawing No.
	RD 138000 m to RD 141000 m	2633
6.369	Canal Alignment and Longitudinal Section from RD 141000 m to RD 144000 m	PTNL-5900-P-2634
6.370	Canal Alignment and Longitudinal Section from RD 144000 to RD 147000 m	PTNL-5900-P-2635
6.371	Canal Alignment and Longitudinal Section from RD 147000 m to RD 150000 m	PTNL-5900-P-2636
6.372	Canal Alignment and Longitudinal Section from RD 150000 m to RD 153000 m	PTNL-5900-P-2637
6.373	Canal Alignment and Longitudinal Section from RD 153000 m to RD 156000 m	PTNL-5900-P-2638
6.374	Canal Alignment and Longitudinal Section from RD 156000 m to RD 159000 m	PTNL-5900-P-2639
6.375	Canal Alignment and Longitudinal Section from RD 159000 m to RD 162000 m	PTNL-5900-P-2640
6.376	Canal Alignment and Longitudinal Section from RD 162000 m to RD 165000 m	PTNL-5900-P-2641
6.377	Canal Alignment and Longitudinal Section from RD 165000 m to RD 168000 m	PTNL-5900-P-2642
6.378	Canal Alignment and Longitudinal Section from RD 168000 m to RD 171000 m	PTNL-5900-P-2643
6.379	Canal Alignment and Longitudinal Section from RD 171000 m to RD 174000 m	PTNL-5900-P-2644
6.380	Canal Alignment and Longitudinal Section from RD 174000 m to RD 177000 m	PTNL-5900-P-2645
6.381	Canal Alignment and Longitudinal Section from RD 177000 m to RD 180000 m	PTNL-5900-P-2646
6.382	Canal Alignment and Longitudinal Section from RD 180000 m to RD 183000 m	PTNL-5900-P-2647
6.383	Canal Alignment and Longitudinal Section from RD 183000 m to RD 186000 m	PTNL-5900-P-2648
6.384	Canal Alignment and Longitudinal Section from RD 186000 m to RD 189000 m	PTNL-5900-P-2649
6.385	Canal Alignment and Longitudinal Section from RD 189000 m to RD 191307.40 m	PTNL-5900-P-2650
	CD Structures	
6.386	General Layout Map of Aqueducts and Culverts in Par-Tapi Reach	PTNL-5900-P-2651
6.387	General Layout Map of Aqueducts and Culverts in Tapi-Narmada Reach	PTNL-5900-P-2652

Plate No.	Description	CWC Drawing No.
6.388	General Layout Map of Superpassage in Par-Tapi and Tapi-Narmada Reach	PTNL-5900-P-2653
6.389	General Layout Map of Head / Cross Regulator at Par-Tapi and Tapi-Narmada Reach	PTNL-5900-P-2654
6.390	General Layout Map of Canal Syphons and Syphon Aqueduct in Par-Tapi Reach	PTNL-5900-P-2655
6.391	General Layout Map of Canal Syphons and Syphon Aqueduct in Tapi-Narmada Reach	PTNL-5900-P-2656
6.392	General Layout Map of Road and Railway Bridges in Par-Tapi Reach	PTNL-5900-P-2657
6.393	General Layout Map of Road and Railway Bridges in Tapi-Narmada Reach	PTNL-5900-P-2658
6.394	Typical Details of Double Lane Road Bridge Across Canal of Bed Width 15 m	PTNL-5900-P-2659
6.395	Typical Details of Double Lane Road Bridge Across Canal of Bed Width 21.80 m	PTNL-5900-P-2660
6.396	Typical Details of Double Lane Road Bridge Across Canal of Bed Width 5.50 m	PTNL-5900-P-2661
6.397	Typical Details of Double Lane Road Bridge Across Canal of Bed Width 8.50 m	PTNL-5900-P-2662
6.398	Typical Details of Single Lane Road Bridge Across Canal of Bed Width 15 m	PTNL-5900-P-2663
6.399	Typical Details of Single Lane Road Bridge Across Canal of Bed Width 21.80 m	PTNL-5900-P-2664
6.400	Typical Details of Single Lane Road Bridge Across Canal of Bed Width 5.50 m	PTNL-5900-P-2665
6.401	Typical Details of Single Lane Road Bridge Across Canal of Bed Width 8.50 m	PTNL-5900-P-2666
6.402	Typical Details of Aqueducts in the Reach RD 0.000 km to RD 60.070 km and Feeder Canals	PTNL-5900-P-2667
6.403	Typical Details of Aqueducts in the Reach RD 60.070 km to RD 108.250 km	PTNL-5900-P-2668
6.404	Typical Details of Aqueducts in the Reach RD 108.250 km to RD 129.600 km	PTNL-5900-P-2669
6.405	Typical Details of Aqueducts in the Reach RD 129.600 km to RD 177.736 km	PTNL-5900-P-2670
6.406	Typical Details of Superpassages	PTNL-5900-P-2671
6.407	Typical Details of Syphon Aqueducts	PTNL-5900-P-2672

Plate No.	Description	CWC Drawing No.
6.408	Typical Details of Canal Syphons	PTNL-5900-P-2673
6.409	Typical Details of Feeder Canal Out Fall	PTNL-5900-P-2674
6.410	Typical Details of Pipe Culverts / Box Culvert	PTNL-5900-P-2675
6.411	Typical Details of Cross Regulator	PTNL-5900-P-2676
6.412	Typical Details of Head Regulator (Type A&B) and Escape on Main Canal Escape	PTNL-5900-P-2677
6.413	Construction Adit (5.50 m X 5.75 m, D-Shape) Typical Excavation and Rock Support Details of Tunnels in Par-Tapi Reach	PTNL-5900-P-2678
6.414	Typical Concrete Lining and Grouting Details of Tunnels in Par-Tapi Reach	PTNL-5900-P-2679
6.415	Typical Construction Tunnel Portal Excavation Support Details of Entry and Exit Portal of Tunnels in Par-Tapi Reach	PTNL-5900-P-2680